

AL/OE-TR-1996-0080



**CONTROL EFFICIENCY DETERMINATION OF
SUDDEN EXPANSION INCINERATOR
BLDG 348, KELLY AFB, TEXAS**

**A
R
M
S
T
R
O
N
G

L
A
B
O
R
A
T
O
R
Y**

Robert J. O'Brien, Captain, USAF, BSC

**OCCUPATIONAL AND ENVIRONMENTAL HEALTH DIRECTORATE
Bioenvironmental Engineering Division
2402 E Drive
Brooks Air Force Base, TX 78235-5114**

June 1996

DTIC QUALITY INSPECTED 4

Final Technical Report for the Period 19 July 1995 to 11 January 1996

Approved for public release; distribution is unlimited.

19960702 015

**AIR FORCE MATERIEL COMMAND
BROOKS AIR FORCE BASE, TEXAS**

NOTICES

When government drawings, specifications, or other data are used for any purpose other than in connection with a definitely Government-related procurement, the United States Government incurs no responsibility or any obligation whatsoever. The fact that the Government may have formulated or in any way supplied the said drawings, specifications, or other data, is not to be regarded by implication, or otherwise in any manner construed as licensing the holder or any other person or corporation; or as conveying any rights or permission to manufacture, use, or sell any patented invention that may in any way be related thereto.

The mention of trade names or commercial products in this publication is for illustration purposes and does not constitute endorsement or recommendation for use by the United States Air Force.

The Office of Public Affairs has reviewed this report, and it is releasable to the National Technical Information Service, where it will be available to the general public, including foreign nationals.

This report has been reviewed and is approved for publication.

Government agencies and their contractors registered with Defense Technical Information Center (DTIC) should direct requests for copies to: DTIC, Building #5, Cameron Station, Alexandria VA 22304-6145.

Non-Government agencies may purchase copies of this report from: National Technical Information Service (NTIS), 5285 Port Royal Road, Springfield VA 22161-2103.


Robert J. O'Brien

ROBERT J. O'BRIEN, Capt, USAF, BSC
Consultant, Air Quality Function

James D. Montgomery

JAMES D. MONTGOMERY, Lt Col, USAF, BSC
Chief, Bioenvironmental Engineering
Division

DISCLAIMER NOTICE



THIS DOCUMENT IS BEST
QUALITY AVAILABLE. THE
COPY FURNISHED TO DTIC
CONTAINED A SIGNIFICANT
NUMBER OF PAGES WHICH DO
NOT REPRODUCE LEGIBLY.

REPORT DOCUMENTATION PAGE

Form Approved
OMB No. 0704-0188

Public reporting burden for this collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Washington Headquarters Services, Directorate for Information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302, and to the Office of Management and Budget, Paperwork Reduction Project (0704-0188), Washington, DC 20503.

1. AGENCY USE ONLY (Leave blank)	2. REPORT DATE June 1996	3. REPORT TYPE AND DATES COVERED Final 19 July 1995 - 11 January 1996	
4. TITLE AND SUBTITLE Control Efficiency Determination of Sudden Expansion Incinerator Bldg 348, Kelly AFB, Texas			5. FUNDING NUMBERS
6. AUTHOR(S) Robert J. O'Brien			
7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES) Armstrong Laboratory (AFMC) Occupational and Environmental Health Directorate Bioenvironmental Engineering Division 2402 E Drive Brooks Air Force Base, TX 78235-5114			8. PERFORMING ORGANIZATION AL/0E-TR-1996-0080
9. SPONSORING/MONITORING AGENCY NAME(S) AND ADDRESS(ES)			10. SPONSORING/MONITORING
11. SUPPLEMENTARY NOTES			
12a. DISTRIBUTION/AVAILABILITY STATEMENT Approved for public release; distribution is unlimited		12b. DISTRIBUTION CODE	
13. ABSTRACT (Maximum 200 words) Compliance emissions testing and Volatile Organic Compound (VOC) destruction efficiency determination were conducted on the Sudden Expansion (SUE) Incinerator located at the Kelly AFB Fuel Accessory Test Facility, Bldg 348. Compliance standards and requirements are found in Operating Permit No. 6493, as amended/renewed by the State of Texas on 24 March 1994. The purpose of the Kelly AFB SUE Incinerator is to destroy calibration fluid vapors emitted from fuel accessory test stands located in Bldg 348. The incinerator can also be used to destroy liquid waste calibration fluid by burning it as a supplemental fuel. Emissions testing was conducted during combustion of both vapors and liquid calibration fluid. For purposes of determining the incinerator VOC destruction efficiency, monitoring for Total VOC concentration in the inlet air stream was conducted on 19-20 July 1995. Emissions testing of the incinerator exhaust was conducted on 10-11 January 1996 and included monitoring for Total VOC, oxides of nitrogen (NOx), carbon monoxide (CO), and visible emissions. Results indicate that the SUE Incinerator is in compliance with all applicable emission standards and with the VOC destruction efficiency requirement.			
14. SUBJECT TERMS Kelly AFB Fuel Accessory Test Facility VOC destruction efficiency Test stands			15. NUMBER OF PAGES 132
SUE Incinerator Calibration fluid			16. PRICE CODE
Emissions testing Inlet duct		Exhaust stack	
17. SECURITY CLASSIFICATION OF REPORT Unclassified	18. SECURITY CLASSIFICATION OF THIS PAGE Unclassified	19. SECURITY CLASSIFICATION OF ABSTRACT Unclassified	20. LIMITATION OF ABSTRACT UL

TABLE OF CONTENTS

	<u>Page</u>
INTRODUCTION	1
Background	1
Site Description	1
Applicable Standards and Guidelines	10
METHODS AND MATERIALS	10
RESULTS	24
DISCUSSION	25
RECOMMENDATIONS	25
REFERENCES	29
APPENDIXES:	
A Personnel Information	31
B Calibration Fluid Information	33
C Operating Permit	37
D Field Data	49
E Calibration Data	75
F HP 41 Program Printouts	81
G VOC Analyzer Information	91
H ENERAC 3000 Analyzer Information	97
I Example Calculations	119

List of Figures

<u>Figure No.</u>		<u>Page</u>
1	Locations of Test Stands	2
2	View of a Typical Test Stand	3
3	Flow Diagram of Calibration Fluid Use	5
4	Flow Diagram of Vapor Ventilation System	6
5	View of Kelly AFB's SUE Incinerator	7
6	Schematic of a Model F5,000 SUE Incinerator	8
7	Schematic of Burner Combustion Process	9
8	Flow Diagram of Fuel and Vapor Input into SUE Incinerator	11
9	View of Inlet Duct Sampling Ports	13
10	Locations of Inlet Duct Sampling Ports	14
11	Locations of Inlet Duct Sampling Points for Velocity, Temperature, and Moisture	14
12	View of Exhaust Stack	15
13	Locations of Exhaust Stack Sampling Ports	17
14	Locations of Exhaust Stack Sampling Points for Velocity, Temperature, and Moisture	18
15	Schematic of Method 5 Sampling Train	19
16	View of Meter Box	20
17	View of VOC Analyzer	23
18	View of ENERAC 3000 Analyzer	23

List of Tables

<u>Table No.</u>		<u>Page</u>
1	Inlet Duct Sampling Results	26
2	Exhaust Stack Sampling Results	27
3	VOC Destruction Efficiency Data	28

**CONTROL EFFICIENCY DETERMINATION OF
SUDDEN EXPANSION INCINERATOR, BLDG 348,
KELLY AFB, TEXAS**

INTRODUCTION

Background

On 19-20 Jul 95 and 10-11 Jan 96, emissions testing was conducted on the Sudden Expansion (SUE) Vapor Incinerator located at the Kelly AFB Fuel Accessory Test Facility (Bldg 348). Testing was performed by the Air Quality Function of the Air Force Armstrong Laboratory. This survey was requested by the Kelly AFB Environmental Management Office to satisfy State of Texas permit requirements. Pollutants monitored during this survey included Total Volatile Organic Compounds (VOC), Oxides of Nitrogen (NO_x), and Carbon Monoxide. Personnel involved with on-site testing are listed in Appendix A.

Site Description

The Kelly AFB Fuel Accessory Test Facility performs testing of F-100 unified fuel control and nozzle units. The inspection process involves passing a calibration fluid (Stoddard solvent, Military Specification MIL-C-7024D Type II) through fuel control units which are set up in functional test stands. Information on the calibration fluid is found in Appendix B. The test stands are large computer-controlled modules which simulate actual operation of the fuel control assemblies.^{1,2,3} There are currently 57 test stands located in Bldg 348. Figure 1 provides a layout of Bldg 348's 1st floor showing the locations of the test stands. A view of a typical test stand is shown in Figure 2.

At each test stand, fuel control units are tested directly over a sink equipped with a down draft ventilation system. The calibration fluid used for testing is pumped from a 500 gallon (gal) reservoir located at each test stand. Testing of the fuel control units is accomplished using one of two configurations, closed loop or open body, depending on which section of the fuel control assembly is being tested. In the closed loop configuration, calibration fluid is pumped through the fuel control unit in a closed system. After the test is completed, the flow control unit is disconnected from the test stand and any residual calibration fluid is dumped into the sink. In the open body configuration, calibration fluid is continuously pumped through the fuel control unit and directly into the sink.^{1,2}

Calibration fluid dumped into the test stand sink is drained back into the 500 gal reservoir. The fluid in the reservoir is




Figure 1. Locations of Test Stands.




Figure 2. View of a Typical Test Stand.

reused for testing until the lab determines (through visual, specific gravity, and viscosity tests) that the fluid is unuseable, at which point it is considered spent (waste) fluid.³ The spent calibration fluid is then drained out and replaced with clean fluid. Vapors from the calibration fluid dumped into the sink are captured by the ventilation system. 24 of the 57 test stands are ventilated to the SUE Incinerator while the other 33 test stands are vented to the atmosphere.

The calibration fluid used for testing the fuel control units is stored in two 20,000 gal underground storage tanks located at the northeast side of Bldg 348 (see Fig. 1). One tank supplies the clean fluid to the 500 gal reservoirs while the other tank receives the spent fluid drained from the reservoirs. Both tanks are vented to the sink vapor air entering the SUE Incinerator system.^{1,2,3} A flow diagram showing calibration fluid use at a typical test stand is presented in Figure 3.

A Robinson Industries blower is used to draw calibration fluid vapors through the ventilation system and into the SUE Incinerator. The blower is rated at 20,000 standard cubic feet per minute (SCFM) and 250 horsepower (hp).³ A flow diagram showing the vapor ventilation system is presented in Figure 4.

The SUE Incinerator (Model F20,000 manufactured by Kaiser Marquardt) consists of four 5,000 SCFM stainless steel burners equipped with integral recuperative heat exchangers which pre-heat incoming air. The incinerator is located in the courtyard on the northeast side of Bldg 348 (see Fig. 1). A view of the SUE Incinerator is shown in Figure 5. A schematic of a similar single burner SUE Incinerator (Model F5,000) is shown in Figure 6. Each burner of the SUE Incinerator includes a cylindrical combustion chamber which is joined to a smaller inlet pipe by a flat circular plate. Fuel nozzles protrude through the flat plate into the combustion chamber. The sudden expansion between the smaller inlet duct and the combustion chamber acts as a flame holder permitting stable combustion over a wide range of pressures, temperatures, and flows.³ A schematic showing the combustion process within a typical burner is presented in Figure 7.

The SUE Incinerator is currently fueled with either natural gas or natural gas supplemented with waste calibration fluid. Although the State operating permit also allows Kelly AFB to use waste shelf life oil as a supplemental fuel, shelf life oil is currently not burned in the SUE Incinerator. The waste calibration fluid burned by the SUE Incinerator comes from the "Spent" 20,000 gal underground storage tank located at Bldg 348 and from a 30,000 gal aboveground storage tank located at Bldg




Figure 3. Flow Diagram of Calibration Fluid Use.




Figure 4. Flow Diagram of Vapor Ventilation System.




Figure 5. View of Kelly AFB's SUE Incinerator.




Figure 6. Schematic of a Model F5,000 SUE Incinerator.

Exhaust | Inlet | 1 of 4 Cylindrical 5000 SCFM Burners of the Incinerator




Figure 7. Schematic of Burner Combustion Process.

345.³ A flow diagram showing fuel and vapor input into the SUE Incinerator is presented in Figure 8.

Applicable Standards and Guidelines

The emission standards, destruction efficiency, and operating requirements for the SUE Incinerator are specified in Texas Natural Resource Conservation Commission (TNRCC) Permit No. 6493, as amended/renewed on 24 Mar 94.⁴ The entire permit is located in Appendix C and the major provisions applicable to the SUE Incinerator are summarized below:

1. The maximum allowable emission rates for VOC are 5.53 pounds per hour (lb/hr) and 24.20 tons per year (TPY).
2. The maximum allowable emission rates for NO_x are 7.69 lb/hr and 33.70 TPY.
3. The maximum allowable emission rates for CO are 21.80 lb/hr and 95.00 TPY.
4. Opacity of emissions from the SUE Incinerator stack must not exceed 5 percent averaged over a six-minute period.
5. A VOC destruction efficiency of 98 percent for the SUE Incinerator shall be demonstrated while burning Stoddard solvent and shelf life oils.
6. The exhaust exit gas temperature of the SUE Incinerator must be continuously monitored and recorded to ensure a minimum temperature of 1450°F is maintained whenever burning VOCs, Stoddard solvent, or shelf life oils.
7. Records listed under Item 10 of the permit (e.g., quantity of liquid fuel burned, hours of incinerator operation, incinerator temperature charts, etc.) shall be maintained for a period of 2 years.

METHODS AND MATERIALS

To determine compliance with the TNRCC Operating Permit, sampling was conducted on both the inlet and outlet sides of the SUE Incinerator. Sampling on the inlet side included measurements for VOC, moisture, temperature, and velocity determination. The velocity was multiplied by the cross-sectional area of the duct to calculate the duct gas flow rate. Sampling on the outlet (exhaust) side of the SUE Incinerator included measurements for VOC, NO_x, CO, Opacity, moisture, temperature, velocity, oxygen (O₂), and carbon dioxide (CO₂).

Process Flow Diagram




Figure 8. Flow Diagram of Fuel and Vapor Input into SUE Incinerator.

The stack gas velocity was multiplied by the cross-sectional area of the stack to calculate the stack gas flow rate. Measurements for moisture, O₂, and CO₂ were required for gas molecular weight determination. Field data from both the inlet and exhaust sampling are found in Appendix D.

The locations of the port holes and sampling points were determined using EPA Method 1. For velocity measurements, Method 1 requires the port holes to be located a minimum of 2 duct diameters downstream and 0.5 duct diameters upstream of the nearest flow disturbances. All EPA Methods used in this survey are found in 40 Code of Federal Regulations, Part 60 (40 CFR 60).⁵

Sampling of the inlet gas stream was performed on a horizontal rectangular duct which is 5' high, 2' wide, and 8' 7" long. This section of duct is located in a small room (closet) adjacent to the SUE Incinerator (see Fig. 1). The effective inside diameter of this section of duct was calculated to be 2.86 feet using the equation $2HW/(H+W)$ where **H** equals the height and **W** equals the width. Four port holes, located on the same vertical plane, were used for measuring the velocity, temperature, and moisture. These four port holes are located approximately 5.75 feet (2.0 duct diameters) downstream from the nearest disturbance. A fifth port hole, located approximately 1.5 feet (0.52 duct diameters) downstream from the first four port holes, was used to monitor Total VOC. A view of the inlet duct sampling ports is shown in Figure 9. In accordance with EPA Method 1, a total of 16 sampling points were used for measuring the velocity, temperature, and moisture. Total VOC were measured at a single point in the cross-sectional center of the duct. Figure 10 shows the locations of the five port holes for the inlet duct. Figure 11 shows the locations of the 16 sampling points used for measuring the velocity, temperature, and moisture.

Sampling of the exhaust gas stream was performed on the 30' high vertical stack located in the same courtyard as the SUE Incinerator. A view of the exhaust stack is shown in Figure 12. The exhaust stack is triangular with the inside opening having two 4' sides and one 5.66' side. The effective inside diameter of this stack was calculated to be 2.34 feet using the equation $4A/P$ where **A** equals the cross-sectional area and **P** equals the perimeter. Four port holes (located on the same horizontal plane) were used for measuring the velocity, temperature, and moisture. These port holes are located approximately 7 feet (3 stack diameters) downstream from the nearest disturbance (i.e., the horizontal exhaust duct connected to the side of the stack). A fifth port hole, located approximately 2 feet (0.85 stack diameters) above the first four port holes, was used to monitor the gaseous parameters (i.e., O₂, CO₂, NO_x, CO, and VOC). In




Figure 9. View of Inlet Duct Sampling Ports.




Figure 10. Locations of Inlet Duct Sampling Ports.




Figure 11. Locations of Inlet Duct Sampling Points for Velocity, Temperature, and Moisture.




Figure 12. View of Exhaust Stack.

accordance with EPA Method 1, a total of 16 sampling points was used for measuring the velocity, temperature, and moisture. The concentrations of O₂, CO₂, NO_x, CO, and VOC were measured at a single point in the geometric cross-sectional center of the stack. Figure 13 shows the locations of the five port holes for the exhaust stack. Figure 14 shows the locations of the 16 sampling points used for measuring the velocity, temperature, and moisture.

Prior to sampling at both the inlet and outlet locations, the degree of cyclonic flow was determined by measuring the gas rotational angle at each of the 16 sampling points chosen for velocity, temperature, and moisture monitoring. Measurements were made using a Type S pitot tube, a 10-inch inclined-vertical manometer, an angle finder, and the procedures described in Paragraph 2.4 of EPA Method 1. Flow conditions are considered acceptable when the arithmetic mean average of the rotational angles is 20 degrees or less. Rotational angle measurements showed the air flow in both the inlet duct and exhaust stack to be within the acceptable limit. Preliminary velocity, temperature, and static pressure readings were also taken at the same time the cyclonic flow measurements were conducted.

The moisture, velocity, and temperature of the exhaust stack gas were determined using an EPA Method 5 sampling train. The train consisted of a button-hook probe nozzle, heated stainless steel probe, heated glass-fiber filter, impingers, and a pumping/metering device (meter box). A schematic of the Method 5 sampling train is shown in Figure 15 and a view of the meter box is shown in Figure 16. Calibration data for the Method 5 equipment are found in Appendix E. Calibrations were performed in accordance with EPA's Quality Assurance Handbook.⁶ The probe nozzle was sized (with a micrometer) prior to sampling using EPA Method 5 criteria. Stack gas velocity pressure was measured at the nozzle tip using a Type S pitot tube connected to a 10-inch inclined-vertical manometer and the procedures described in EPA Method 2. Type K thermocouples were used to measure stack gas as well as sampling train temperatures. The probe liner was heated to minimize moisture condensation. The heated filter was used to filter out particulates prior to the impingers. The impinger train consisted of four glass impingers in series. The impinger train was placed in an ice bath which enabled the stack gas moisture to condense into the impingers. The first, third, and fourth impingers were of modified Greenburg-Smith design while the second impinger was a standard Greenburg-Smith type. The first and second impingers each contained 200 milliliters (ml) of distilled water, the third impinger was empty, and the fourth impinger contained 200 grams (g) of silica gel. The pumping and metering system was used to control and monitor the sample gas flow rate. In accordance with EPA Method 4, moisture sampling




Figure 13. Locations of Exhaust Stack Sampling Ports.

Top View




Figure 14. Locations of Exhaust Stack Sampling Points for Velocity, Temperature, and Moisture.




Figure 15. Schematic of Method 5 Sampling Train.



Figure 16. View of Meter Box.

was conducted at a constant flow rate and for an equal time (3.75 minutes) at each of the 16 sampling points. The velocity and flow rate of the stack gas were calculated using the EPA's HP 41 "METH 2" Calculator Program. The percent moisture of the exhaust stack gas was calculated using the EPA's Hewlett-Packard 41 (HP 41) "METH 4" Calculator Program.⁷ Printouts from all the HP 41 programs run for this survey are found in Appendix F.

The moisture and temperature of the inlet duct gas were determined using wet bulb-dry bulb temperature readings. Measurements were taken at each of the 16 sampling points using mercury-in-glass thermometers. The percent moisture of the inlet duct gas was calculated using the EPA's HP 41 "WBDB" Calculator Program.

The velocity of the inlet duct gas was determined using a Type S pitot tube and a 10-inch inclined-vertical manometer. Calculations for the velocity and flow rate of the inlet duct gas were performed using the EPA's HP 41 "METH 2" Calculator Program.

The VOC concentration in both the inlet duct and exhaust stack gas was measured with a JUM Model 3-300A Flame Ionization Detector (FID) analyzer and the procedures described in EPA Method 25A. Prior to entering the analyzer, the sample gas traveled through a sampling system consisting of a heated stainless steel probe, a particulate filter, and a heated Teflon line. The sample was drawn through the system by a heated pump built into the analyzer. A 40% Hydrogen/60% Helium gas mixture was used as the fuel for the FID. A view of the VOC analyzer is shown in Figure 17. Information on the VOC analyzer, including calibration procedures, is found in Appendix G. A member of the survey team recorded VOC concentration measurements at 1-minute intervals during each sampling run. Measurements were in units of parts per million by volume (ppmv) as propane. The average VOC concentration for each sampling run was later converted to a mass emission rate in pounds per hour (lb/hr) using the following equation:

$$E = (C) \times (MW) \times (FR) \times (1.55 \times 10^{-7}) \quad (1)$$

Where,

E = The pollutant emission rate in pounds per hour (lb/hr) [Note - VOC emission rate is reported as propane].

C = The measured pollutant concentration in ppmv.

MW = The molecular weight of the pollutant [Note - for VOC, the molecular weight of the calibration gas (propane) is used].

FR = The flow rate of the stack (or duct) gas in DSCFM.

1.55×10^{-7} = Conversion Factor $[(\text{min} \cdot \text{g} \cdot \text{mole} \cdot \text{lb}) / (\text{hr} \cdot \text{g} \cdot \text{ft}^3)]$

Initial plans were to sample for NO_x , O_2 , and CO_2 in the exhaust stack gas with a Continuous Emission Monitoring (CEM) system manufactured by the Anarad Corporation. This system includes a sample conditioning/flow control module, a chemiluminescent NO_x analyzer, an infrared CO_2 analyzer, and an electrochemical O_2 analyzer. Unfortunately, because of mechanical problems with the sample flow control module, the analyzers could not be properly calibrated. Therefore, sampling for these parameters was instead accomplished using a backup method consisting of an ENERAC 3000 portable analyzer. This analyzer uses an electrochemical cell to measure O_2 concentration. NO_x concentration is computed by the analyzer by adding together the concentrations of nitric oxide (NO) and nitrogen dioxide (NO_2), both of which are measured via electrochemical cells. The analyzer computes CO_2 based on the O_2 content and the type of combustion fuel. A member of the survey team recorded NO_x , O_2 and CO_2 concentration measurements at 2-minute intervals during each sampling run. O_2 and CO_2 measurements were in units of percent while NO_x measurements were in units of ppm as NO_2 . The average NO_x concentration for each sampling run was later converted to a mass emission rate (lb/hr) using Equation 1. A view of the ENERAC 3000 analyzer is shown in Figure 18. Specifications and information, including calibration procedures, for the ENERAC 3000 analyzer are found in Appendix H.

Sampling for CO in the exhaust stack gas was attempted using an Anarad Model AR-411 non-dispersive infrared (NDIR) analyzer. However, due to excessive drift, this instrument was not used. Instead, CO was determined using the ENERAC 3000 analyzer. The analyzer measures CO concentration via an electrochemical cell. A member of the survey team recorded CO concentration measurements at 2-minute intervals during each sampling run. Measurements were in units of ppm. The average CO concentration for each sampling run was later converted to a mass emission rate (lb/hr) using Equation 1.

The rate of liquid waste calibration fluid (lb/hr Stoddard solvent) combusted in the SUE Incinerator during each sampling run was recorded from the incinerator's main console.

The VOC destruction efficiency of the SUE Incinerator was calculated using the following equation:

$$\text{DE} = [(CF - E_{ex})/CF] \times 100 \quad (2)$$

Where,

DE = Destruction Efficiency (%)

CF = Calibration Fluid combusted by SUE Incinerator (lb/hr as Stoddard solvent) [Note - includes both the VOC vapors in the inlet gas stream and the liquid waste calibration fluid



Figure 17. View of VOC Analyzer.




Figure 18. View of ENERAC 3000 Analyzer.

burned as supplemental fuel]
 E_{ex} = VOC emission rate in exhaust stack (lb/hr as Stoddard solvent)

The VOC destruction efficiency was calculated based on the total Stoddard solvent burned by the incinerator. This includes the VOC vapors in the inlet gas stream (i.e., vapors removed from the test stands in Building 348) and the liquid waste Stoddard solvent burned as a supplemental fuel. Since the liquid waste solvent is included, it was necessary to convert both the inlet VOC vapor concentration and the exhaust VOC concentration from "ppmv as propane" to "ppmv as Stoddard solvent." This was done by first converting "ppmv as propane" to "ppmv as carbon" by multiplying by 3 (the carbon equivalent correction factor) in accordance with EPA Method 25A.⁵ The concentration in "ppmv as carbon" was then converted to "ppmv as Stoddard solvent" by dividing by 7.05 (response factor determined by a contractor, Engineering Science, during emissions testing performed at Bldg 348 in Sep 92).² The molecular weight of Stoddard solvent (140) was then used with Equation 1 to convert "ppmv as Stoddard solvent" to a mass flow rate (lb/hr Stoddard solvent).

Example calculations, using Equations 1 and 2 above, are shown in Appendix I.

Opacity (visible emission) readings were recorded by a person who is certified by the Texas Natural Resources Conservation Commission. Three opacity runs were conducted. Each run consisted of taking readings every 15 seconds for 30 minutes. Due to a man-power shortage, each opacity run was conducted shortly before a stack sampling run. The incinerator was operated under the same conditions for the opacity runs and the corresponding stack sampling runs.

RESULTS

Sampling of the inlet duct gas stream was performed on 19-20 Jul 95 during normal test stand operations in Bldg 348. Although the SUE Incinerator was not operational at this time, permission to proceed with the inlet testing was given by the TNRCC. Table 1 provides a summary of the results from the inlet testing. The average VOC mass flow rate for the three sampling runs was 10.2 lb/hr as propane.

The SUE Incinerator became fully operational in early Jan 96. Sampling of the exhaust stack gas was therefore performed on 10-11 Jan 96 during normal test stand operations in Bldg 348. During testing, the incinerator was operated at approximately 70% capacity. The incinerator fuel combustion rate during all three

sampling runs was approximately 108 pounds per hour (lb/hr) of liquid waste calibration fluid and 4,000 standard cubic feet per hour (scfh) of natural gas. Table 2 provides a summary of the results from the exhaust testing. In brief, the average VOC mass emission rate for the three sampling runs was 0.66 lb/hr as propane, the average NO_x mass emission rate was 1.9 lb/hr as NO₂, and the average CO emission rate was 3.4 lb/hr. All visible emission readings showed 0 percent opacity.

Based on the VOC inlet and VOC exhaust mass emission rates and on the amount of liquid waste calibration fluid burned, the average VOC destruction efficiency was calculated to be 99.3 percent. A summary of the data used to calculate this destruction efficiency is found in Table 3.

DISCUSSION

Results show that the VOC, NO_x, and CO mass emission rates from the SUE Incinerator were all well below TNRCC Permit limits. With no opacity readings above 0 percent, the SUE Incinerator also met the TNRCC limit for opacity. Finally, the 99.3 percent destruction efficiency demonstrated by the SUE Incinerator was above the TNRCC minimum requirement of 98 percent.

RECOMMENDATIONS

The following recommendations are provided to ensure compliance with TNRCC Permit No. 6493 regarding the Bldg 348 test stands and the SUE Incinerator:

1. Ensure the temperature inside the incinerator is always maintained above 1450° F during operation.
2. Ensure the following records are maintained on base for a period of at least two years:
 - a. Records of the amount of calibration fluid purchased and of waste calibration fluid sent to reclamation.
 - b. Inventory records on the contents of the Calibration Fluid Supply Tank and the Waste Calibration Fluid Storage Tank.
 - c. Records of the quantity of calibration fluid (Stoddard solvent) or shelf life oil burned in the SUE Incinerator.
 - d. Records of the hours of operation of the SUE Incinerator.

Table 1. Inlet Duct Sampling Results

	Run 1	Run 2	Run 3	Average
Test Date	19 Jul 95	20 Jul 95	20 Jul 95	
Test Time (Military)	1256-1356	1042-1142	1327-1427	
Station Pressure ("Hg)	29.260	29.205	29.205	
Duct Static Pressure ("H ₂ O)	-1.46	-1.46	-1.46	
Avg Dry Bulb Temperature (°F)	82	80	84	
Avg Wet Bulb Temperature (°F)	70	70	70	
Gas Moisture Content (%H ₂ O)	2.1	2.2	2.0	
Gas Oxygen Content (%O ₂) ¹	20.9	20.9	20.9	
Avg Velocity Pressure ("H ₂ O)	0.10	0.10	0.10	
Avg Gas Velocity (ft/sec)	18	18	18	
Actual Gas Flow Rate (ACFM)	10,858	10,901	10,847	10,869
Corrected Flow Rate (DSCFM)	10,094	10,132	10,028	10,085
Avg VOC Reading (ppmv) ²	202	100	144	149
VOC Emission Rate (lb/hr) ³	13.9	6.9	9.8	10.2

Units

"Hg = inches of mercury

"H₂O = inches of water

°F = degrees Fahrenheit

%H₂O = percent water

%O₂ = percent oxygen

ft/sec = feet per second

ACFM = actual cubic feet per minute

DSCFM = dry standard cubic feet per minute

ppmv = parts per million by volume

lb/hr = pounds per hour Note: lb/hr = (ppm) (MW) (DSCFM) (1.55 x 10⁷)

Notes

¹ Based on ambient air

² Measured as propane

³ Calculated as propane

Table 2. Exhaust Stack Sampling Results

	Run 1	Run 2	Run 3	Average
Test Date	10 Jan 96	11 Jan 96	11 Jan 96	
Test Start Time (Military)	1416	1155	1442	
Station Pressure ("Hg)	29.305	29.460	29.410	
Stack Static Pressure ("H ₂ O)	-0.20	-0.20	-0.20	
Average Stack Gas Temperature (°F)	606	632	629	622
Stack Gas Moisture Content (%H ₂ O)	2.9	1.7	2.1	2.2
Stack Gas Oxygen Content (%O ₂)	18.8	18.7	18.8	18.8
Stack Gas Carbon Dioxide Content (%CO ₂)	1.6	1.7	1.6	1.6
Stack Gas Velocity (ft/sec)	41	41	42	41
Actual Stack Gas Flow Rate (ACFM)	19,440	19,446	19,940	19,609
Corrected Flow Rate (DSCFM)	9,155	9,097	9,297	9,183
Average CO Reading (ppmv)	91	108	54	84
Average NO _x Reading (ppmv)	26	29	31	29
Average VOC Reading (ppmv as propane)	14.7	9.1	8.1	10.6
CO Emission Rate (lb/hr)	3.6	4.3	2.2	3.4
NO _x Emission Rate (lb/hr as NO ₂)	1.7	1.9	2.1	1.9
VOC Emission Rate (lb/hr as propane)	0.92	0.56	0.51	0.66
Opacity (%)*	0	0	0	0

* Opacity readings were taken just prior to the stack gas sampling with the incinerator operating under the same conditions

Units

"Hg = inches of mercury

"H₂O = inches of water

°F = degrees Fahrenheit

%H₂O = percent moisture

%O₂ = percent oxygen

ft/sec = feet per second

ACFM = actual cubic feet per minute

DSCFM = dry standard cubic feet per minute

ppmv = parts per million by volume

lb/hr = pounds per hour Note: lb/hr = (ppm) (MW) (DSCFM) (1.55 x 10⁻⁷)

TNRCC Permit Limits

CO: 21.80 lb/hr

NO_x: 7.69 lb/hr as NO₂

VOC: 5.53 lb/hr as propane

Opacity: 5%

Table 3. VOC Destruction Efficiency Data

	Run 1	Run 2	Run 3	Average
Corrected Stack Gas Flow Rate (DSCFM)	9,155	9,097	9,297	9,183
Measured Stack Gas VOC Concentration (ppmv as propane)	14.7	9.1	8.1	10.6
Converted Stack Gas VOC Concentration (ppmv as Stoddard solvent)	6.3	3.9	3.4	4.5
Converted Stack Gas VOC Emission Rate (lb/hr as Stoddard solvent)	1.25	0.77	0.69	0.90
Corrected Inlet Air Flow Rate (DSCFM)				10,085*
Measured Inlet Air Stream Solvent Vapor Concentration (ppmv as propane)				149*
Converted Inlet Air Stream Solvent Vapor Concentration (ppmv as Stoddard solvent)				63.4
Converted Inlet Air Stream Solvent Vapor Rate (lb/hr as Stoddard solvent)				13.9
Liquid Waste Solvent Consumption Rate (lb/hr Stoddard solvent)	108	107	108	107.7
Total Stoddard Solvent Consumption Rate (lb/hr)	121.9	120.9	121.9	121.6
VOC Destruction Efficiency (%)	99.0	99.4	99.4	99.3

* Determined from testing performed in Jul 95

Units

DSCFM = dry standard cubic feet per minute

ppmv = parts per million by volume

lb/hr = pounds per hour Note: lb/hr = (ppm) (MW) (DSCFM) (1.55×10^{-7})

TNRCC Permit Requirement: VOC Destruction Efficiency \geq 98%

e. Charts from the temperature monitor for the SUE Incinerator.

3. Ensure another VOC destruction efficiency determination is performed on the SUE Incinerator if the base decides to use waste shelf life oil as a supplemental fuel.

4. Ensure the VOC emissions from the 33 test stands vented directly to the atmosphere are calculated and tabulated monthly. The emission calculations shall be based on calibration fluid usage (i.e., mass-balance). The calculated emissions must also be reported in the annual base air emissions inventory.

Armstrong Laboratory will remain active in supporting the base's present and future needs.

REFERENCES

1. USAF Occupational and Environmental Health Laboratory, Volatile Organic Compound (VOC) Testing at Building 348, Kelly AFB TX, USAFOEHL Report 87-147EQ0094LEF, Brooks AFB TX, November 1987.
2. Engineering-Science, Inc., VOC Testing of the Carbon Adsorption Unit, Building 348, Kelly Air Force Base, Texas, Austin TX, April 1993
3. San Antonio Air Logistics Center, Vapor Incineration System Program, Kelly AFB TX, 12 June 1995
4. Texas Natural Resource Conservation Commission, Permit Number 6493, Austin TX, 24 March 1994
5. Office of the Federal Register National Archives and Records Service, Code of Federal Regulations, Title 40, Part 60, Washington DC, July 1994.
6. U.S. Environmental Protection Agency, Quality Assurance Handbook for Air Pollution Measurement Systems: Volume III. Stationary Sources Specific Methods, EPA/600/4-77/-07b, Research Triangle Park NC, December 1984
7. U.S. Environmental Protection Agency, Source Test Calculation and Check Programs for Hewlett-Packard 41 Calculators, EPA-340/1-85-018, Research Triangle Park NC, May 1987

APPENDIX A
Personnel Information

PERSONNEL INFORMATION

1. Armstrong Laboratory Air Quality Test Team

Maj Larry Kimm, Chief, Air and Hazardous Waste Branch
Capt Robert O'Brien, Air Quality Consultant, Project Officer
Capt Gregory Durand, Air Quality Consultant
Capt T.C. Moore, Air Quality Meteorologist
2Lt Kyle Blasch, Air Quality Consultant
MSgt Kurt Jagielski, Air Quality Technician
SSgt Michael Dobbins, Air Quality Technician

AL/OEBQ
2402 E Drive
Brooks AFB TX 78235-5114
Phone: DSN 240-3305
Comm (210) 536-3305

2. Kelly AFB On-Site Representatives

Capt Michael Blank, Air Quality Program Manager
SA-ALC/EMC
307 Tinker Dr. (Bldg 306)
Kelly AFB, TX 78241-5917
Phone: DSN 945-3100 ext 306
Comm (210) 925-3100 ext 306

Mr Robert Burns, Mechanical Engineer
SA-ALC/LPPEC
505 Perrin Road (Bldg 324)
Kelly AFB, TX 78241-6435
Phone: DSN 945-8655
Comm (210) 925-8655

Mr John Jurek, Mechanical Engineer
SA-ALC/LPPEC
505 Perrin Road (Bldg 324)
Kelly AFB, TX 78241-6435
Phone: DSN 945-7581
Comm (210) 925-7581

3. Kaiser Marquardt On-Site Representative

Mr Ray Wieveg, Design Engineer
Kaiser Marquardt
16555 Saticoy Street
Van Nuys, CA 91406-1739
Phone: (818) 989-6542

APPENDIX B
Calibration Fluid Information

MIL-C-7024D Calibrating Fluids, Aircraft Fuel System Components

Rev D: 30 Aug 1990 Classification: Type II Special Run
FSCM (CAGE): 81349 Stoddard Solvent CH4*B6, M.W. = 140
NSN: 6850-00-656-0810

----- VSMF ----- Chemical Family: Paraffinic and Naphthenic Hydrocarbons

Locator Code: H-24-15

Film Loc: X552-1268

Microfiche: 011268 Loc: 0163D06 Synonyms: Stoddard Solvent, Mineral Spirits, Short Range Mineral Spirits

Specific Gravity: 0.770 ± 0.005 @ 60°F, 15.6°C ASTM Test Method D1298
Viscosity: 1.17 ± 0.05 centistokes @ 77°F, 25°C ASTM Test Method D445
Particulate Matter (min): 2.0 mg/liter ASTM Test Method D2276
Flash Point (min): 100°F, 38°C ASTM Test Method D56
Initial/Final Boiling Points: 300°F/410°F ASTM Test Method D86
Aromatics, Volume Percent (max): 20.0% ASTM Test Method D1319
Olefins, Volume Percent (max): 5.0% ASTM Test Method D1319
Total Acid Number (max): 0.015 mg KOH/g ASTM Test Method D3242
Gum, Existent (max): 5.0 mg/100 ml ASTM Test Method D381
Vapor Pressure: 0.1 psi @ 100°F ASTM Test Method D323

Autoignition Temperature: >400°F Percent Volatile: essentially 100%
Flammability Limits in Air:
 Lower Explosive Limit: 0.9% Upper Explosive Limit: 6.0%
Vapor Density (air=1): <1.0
Solubility in Water: Negligible Water Weight: 8.33 lbs/gal at 80°F
Appearance and Odor: Water white liquid with mild hydrocarbon odor

NFPA Classification:
 Health: Slightly Hazardous (1) Fire: Moderate (2)
 Reactivity: Stable (0) Specific Hazard: not applicable
 Weight: 6.47 lbs/gal at 60°F and 6.34 lbs/gal at 80°F

SUPPLIERS

1. Solvents & Chemicals, Inc.
 4707 Shank Road, P.O. Box 490
 Pearland, Texas 77588-0490
 Tel: (713) 485-5377

2. Southwest Solvents & Chemicals
 225 Two Twenty-One Drive
 Buda, Texas 78610
 Tel: (512) 282-6390

FUELS COMPARISON

FUEL	FLASHPOINT (°F)	SPEC GRAVITY (KG/L)	VISCOOSITY (CENTISTOKES)
JP8 MIL-T-83133	100	0.775 min 0.840 max	8.0
JP5/JP8 ST MIL-T-5624N	140	0.815 min 0.845 max	8.5
JP5 MIL-F-5624	140	0.788 min 0.845 max	8.5
CAL FLUID MIL-C-7024D TYPE 2	100	0.765 min 0.775 max	3.3

APPENDIX C
Operating Permit

John Hail, Chairman
Pam Reed, Commissioner
Peggy Carter, Commissioner
Anthony Grigsby, Executive Director



RECEIVED
SA-AUC/EMH/KELLY
FEB 23 PM 1:20

TEXAS NATURAL RESOURCE CONSERVATION COMMISSION

Protecting Texas by Reducing and Preventing Pollution

March 24, 1994

Mr. Lawrence O. Bailey, Jr.
Director, Environmental Management
KELLY AIR FORCE BASE (AFB)
307 Tinker Drive, Building 306
Kelly AFB, Texas 78241-5917

Re: Permit Amendment and Renewal
Permit No. 6493
Fuel Accessory Test Facility
Incinerator
Kelly AFB, Bexar County
Account ID No. SG-0103-F

Dear Mr. Bailey:

This is in response to your permit application, Form PI-1, and renewal application, Form PI-1R, concerning the proposed amendment and renewal of Permit No. 6493. We understand that you propose to replace the current carbon absorption unit with a thermal oxidizer that will achieve 95 percent destruction of the volatile organic compounds (VOC) routed through it.

Pursuant to Texas Natural Resource Conservation Commission (TNRCC) Rule 116.116(a) of 30 Texas Administrative Code §116 (30 TAC §116) (commonly known as Regulation VI), Permit No. 6493 is hereby amended in accordance with your proposal. This information will be incorporated into the existing permit file.

Also, pursuant to TNRCC Rule 116.314(a) of 30 TAC §116, your permit is hereby renewed. Enclosed are new provisions and an emission allowable table. Please attach these to your permit. We will appreciate your carefully reviewing the conditions of the permit and assuring that all requirements are consistently met.

We have enclosed two operations certification forms (Form PI-3A and Form PI-3B). Rule 116.110(b) of 30 TAC §116 (commonly known as Regulation VI) requires you to certify that operations addressed in this permit are in conformance with representations in the permit application.


Mr. Lawrence O. Bailey, Jr.
Page 2

March 24, 1994

Please file these certifications with both the TNRCC Austin New Source Review Program and the appropriate TNRCC regional office in a timely manner as prescribed by rule.

Thank you for your cooperation in sending us the information necessary to evaluate your operations and for your commitment to air pollution control. Please let us know if you have any questions.

Sincerely,



for Anthony C. Grigsby
Executive Director

Enclosures

cc: Mr. James Menke, Air Program Manager, San Antonio
Mr. Sam Sanchez, Chief Sanitarian, Division of
Environmental Services, San Antonio Metropolitan
Health District, City of San Antonio

TEXAS NATURAL RESOURCE CONSERVATION COMMISSION

Office of Air Quality
New Source Review Program
Post Office Box 13087
Austin, Texas 78711-3087



A

FORM PI-3A

Operations Certification (Part 1 of 2) TNRCC Rule 116.110(b)(1)(A)

For facilities permitted by authority of Title 30 Texas Administrative Code, Chapter 116.

This certification must be signed by an individual with process knowledge in a managerial capacity and must be submitted upon completion of construction and prior to start of operation of the authorized facilities.

Permit Number _____

Date of Permit Issuance or Last Amendment: _____

I. Permittee

Permit Issued To: _____
Mailing Address: _____

Technical Contact: (Person, Title, Mailing Address) _____ Telephone: () _____ - _____

II. Permit Unit Information

Permit Unit Name: _____
Location: Nearest City _____ County: _____
TNRCC Air Quality Account Number: _____

III. Construction and Operating Schedule Dates

Start of Construction: _____ Proposed Start of Operation: _____
Completion of Construction: _____

IV. A copy of this certification must be sent to the TNRCC Regional Office.

Regional Office (city) sent to: _____

V. Certification

I, _____

Name - please print or type _____ Title - Owner, Plant Manager, President, Vice President, Environmental Director
state that I have knowledge of the facts herein set forth and that the same are true and correct to the best of my knowledge. I certify that the facilities or changes authorized by the referenced permit have been accomplished as represented, if those representations affect emissions, method of control, or character of emissions.

DATE _____

SIGNATURE _____

Note: Original signature in ink required.

A second certification, FORM PI-3B, must be submitted simultaneously with any report of testing or monitoring results required by the permit or, if no testing or monitoring is required, within 60 days of the commencement of operation.

TEXAS NATURAL RESOURCE CONSERVATION COMMISSION

Office of Air Quality
New Source Review Program
Post Office Box 13087
Austin, Texas 78711-3087



B

FORM PI-3B

Operations Certification (Part 2 of 2)
TNRCC Rule 116.110(b)(1)(B)

For facilities permitted by authority of Title 30 Texas Administrative Code, Chapter 116.

This certification must be signed by an individual with process knowledge in a managerial capacity, and must be submitted simultaneously with any report of testing or monitoring results required by the permit or, if no testing or monitoring is required, within 60 days of the commencement of operation.

Permit Number: _____

Date of Permit Issuance or Last Amendment: _____

Submittal Date of Form PI-3A (Part 1 of Operations Certification): _____

I. Permittee

Permit Issued To: _____
Mailing Address: _____

Technical Contact: (Person, Title, Mailing Address) _____
Telephone: () _____ - _____

II. Permit Unit Information

Permit Unit Name: _____
Location: Nearest City: _____ County: _____
TNRCC Air Quality Account Number: _____ - _____

III. Construction and Operating Schedule Dates

Start of Construction: _____ Start of Operation: _____
Completion of Construction: _____

IV. A copy of this certification must be sent to the TNRCC Regional Office. Regional Office (city) sent to: _____

V. Certification

I, _____

Name - please print or type _____ Title - Owner, Plant Manager, President, Vice President, Environmental Director
I state that I have knowledge of the facts herein set forth and that the same are true and correct to the best of my knowledge. I certify that the facility complies with all terms of the preconstruction permit and that operations of the facility are in compliance with the Texas Clean Air Act (Chapter 382, Texas Health & Safety Code) and the air quality rules of the TNRCC.

DATE _____

SIGNATURE _____

Note: Original signature in ink required.

GENERAL PROVISIONS

6493

1. Equivalency of Methods - It shall be the responsibility of the holder of this permit to demonstrate or otherwise justify the equivalency of emission control methods, sampling or other emission testing methods and monitoring methods proposed as alternatives to methods indicated in the provisions of this permit. Alternative methods shall be applied for in writing and shall be reviewed and approved by the Executive Director prior to their use in fulfilling any requirements of this permit.
2. Sampling Requirements - If sampling of stacks or process vents is required, the holder of this permit must contact the Source and Mobile Monitoring Section of the Texas Natural Resource Conservation Commission (TNRCC) prior to sampling to obtain the proper data forms and procedures. The holder of this permit is also responsible for providing sampling facilities and conducting the sampling operations at his own expense.
3. Appeal - This permit may be appealed pursuant to Rule 103.81 of the Procedural Rules of the TNRCC and Section 382.032 of the Texas Clean Air Act. Failure to take such appeal constitutes acceptance by the applicant of all terms of the permit.
4. Construction Progress - Start of construction, construction interruptions exceeding 45 days and completion of construction shall be reported to the appropriate regional office of the TNRCC not later than 10 working days after occurrence of the event.
5. Recordkeeping - Information and data concerning production, operating hours, sampling and monitoring data, if applicable, fuel type and fuel sulfur content, if applicable, shall be maintained in a file at the plant site and made available at the request of personnel from the TNRCC or any local air pollution control program having jurisdiction. The file shall be retained for at least two years following the date that the information or data is obtained.
6. Maintenance of Emission Control - The facilities covered by this permit shall not be operated unless all air pollution emission capture equipment and abatement equipment are maintained in good working order and operating properly during normal facility operations.

SPECIAL PROVISIONS

6493

EMISSION STANDARDS, FUEL SPECIFICATIONS, AND WORK PRACTICES

1. This permit covers only those sources of emissions listed in the attached table entitled "Emission Sources - Maximum Allowable Emission Rates," and those sources are limited to the emission limits and other conditions specified in the attached table. The annual rates are based on any consecutive 12-month period.
2. Compliance with the Volatile Organic Compound (VOC) emission limitation for the SUE Incinerator (EPN No. 20) shall be demonstrated by monitoring the temperature of the secondary chamber. Compliance with the VOC emissions for test stands vented to the atmosphere will be demonstrated by calculating emissions from carbon compound usage. The emissions shall be tabulated monthly and reported annually with the facility emissions inventory.
3. All waste carbon compounds must be stored in closed containers.
4. Opacity of emissions from the SUE incinerator stack must not exceed 5 percent averaged over a six-minute period.
5. Fuel for the SUE incinerator shall be limited to stoddard solvent, shelf life hydrocarbon materials, and pipeline-quality natural gas containing no more than 0.25 grains hydrogen sulfide and 5.0 grains total sulfur per 100 dscf.
6. The minimum exhaust exit gas temperature of the SUE incinerator of 1450°F must be continuously monitored and recorded whenever burning VOCs, stoddard solvent, or shelf life oils.
7. A copy of this permit shall be kept at the plant site and made immediately available at the request of personnel from the Texas Natural Resource Conservation Commission (TNRCC), Environmental Protection Agency (EPA), or any local air pollution control agency having jurisdiction. In addition, the holder of this permit shall clearly identify all equipment at the facility covered by this permit that has the potential of emitting air contaminants. Permitted emission points shall be clearly identified corresponding to the emission point numbering on the maximum allowable emission rates table. Grandfathered or exempt facilities shall be clearly identified corresponding to the emission point numbering used in the most recent emissions inventory submitted to the TNRCC.

INITIAL DETERMINATION OF COMPLIANCE

8. The holder of this permit shall perform stack sampling and other testing as required to establish the actual pattern and quantities of air contaminants being emitted into the atmosphere from the SUE incinerator stack. The holder of this permit is responsible for providing sampling and testing facilities and conducting the sampling and testing operations at his expense.

A. The appropriate TNRCC regional office in the region where the source is located shall be contacted as soon as testing is scheduled but not less than 45 days prior to sampling to schedule a pretest meeting. The notice shall include:

- (1) Date for pretest meeting.
- (2) Date sampling will occur.
- (3) Name of firm conducting sampling.
- (4) Type of sampling equipment to be used.
- (5) Method or procedure to be used in sampling.

The purpose of the pretest meeting is to review the necessary sampling and testing procedures, to provide the proper data forms for recording pertinent data, and to review the format procedures for submitting the test reports.

A written proposed description of any deviation from sampling procedures specified in permit provision or TNRCC or EPA sampling procedures shall be made available to the TNRCC prior to the pretest meeting. The Regional Manager or the Manager of the Source and Mobil Monitoring Section shall approve or disapprove of any deviation from specified sampling procedures.

Requests to waive testing for any pollutant specified in B of this provision shall be submitted to the TNRCC New Source Review Program.

B. Air contaminants emitted from the incinerator stack to be tested for include (but are not limited to) VOC, nitrogen oxides (NOx), and carbon monoxide (CO).

C. If sampling ports and platforms meeting the specifications set forth in the attachment entitled "Chapter 2, Stack Sampling Facilities" are not required, alternate designs may be approved at the pretest meeting.

- D. Sampling shall occur within 60 days after initial start-up of the SUE incinerator. Requests for additional time to perform sampling shall be submitted to the regional office.
- E. The VOC destruction efficiency of 98 percent for the SUE incinerator while burning stoddard solvent and shelf life oils shall be demonstrated at the maximum test stand VOC generation rate during stack emission testing. Primary operating parameters that enable determination of VOC generation rate shall be monitored and recorded during the stack test. These parameters will be determined at the pretest meeting.
- F. Copies of the final sampling report shall be forwarded to the TNRCC within 90 days after sampling is completed. Sampling reports shall comply with the attached provisions of Chapter 14 of the TNRCC Sampling Procedures Manual. The reports shall be distributed as follows:
 - One copy to the appropriate TNRCC regional office.
 - One copy to the TNRCC New Source Review Program, Austin.
- G. At least two 6-minute visual opacity readings will be taken during the testing.

CONTINUOUS DEMONSTRATION OF COMPLIANCE

- 9. Temperature in the SUE incinerator must be continuously monitored and recorded to ensure the minimum temperature of 1450°F is maintained.

RECORDKEEPING REQUIREMENTS

- 10. The following records shall be maintained by the source for a period of two years and shall be made available to the Executive Director or his designated representative upon request:
 - A. Records of the amount of calibrating fluid purchased and spent calibrating fluid sent to reclamation.

Special Provisions

6493

Page 4

- B. Inventory records on the contents of the Calibrating Fluid Supply Tank and the Spent Calibrating Fluid Storage Tank.
- C. Records of the quantity of standard solvent and shelf life oil burned in the SUE incinerator.
- D. Records of hours of operation of the SUE incinerator.
- E. Charts from the temperature monitor for the SUE incinerator.
- F. Inventory records of additions, recovery, and disposal of all degreasing solvents and cleaning solvents.
- G. Records of inspection and replacement of bags in the grit blast filter system.

Dated 3/24/94

EMISSION SOURCES - MAXIMUM ALLOWABLE EMISSION RATES

6493

This table lists the maximum allowable emission rates and all sources of air contaminants on the applicant's property covered by this permit. The emission rates shown are those derived from information submitted as part of the application for permit and are the maximum rates allowed for these facilities. Any proposed increase in emission rates may require an application for a modification of the facilities covered by this permit.

AIR CONTAMINANTS DATA

Emission Point No. (1)	Source Name (2)	Air Contaminant Name (3)	Emission Rates* #/hr	TPY
7	Vapor Degreaser	VOC	0.80	2.50
8	Drying Oven	VOC	1.81	5.65
9	Vapor Blasting	PM/PM10	0.46	1.44
		VOC	0.10	0.31
10	Abrasive Blasting	PM/PM10	0.03	0.09
11	3 Test Stands	VOC	0.12	0.37
12	3 Test Stands	VOC	0.12	0.37
13	2 Test Stands	VOC	0.05	0.16
14	5 Test Stands	VOC	0.79	2.46
15	4 Test Stands	VOC	0.08	0.25
16	Abrasive Blasting	PM/PM10	0.03	0.09
17	2 Test Stands	VOC	0.21	0.66
18	2 Test Stands	VOC	0.20	0.62
19	Nitric Acid Tank	HNO3	0.05	0.16
20	Sue Incinerator 20,000 SCFM	VOC	5.53	24.20
		NOx	7.69	33.70
		CO	21.80	95.00
21	3 Test Stands	VOC	0.12	0.37
22	3 Test Stands	VOC	0.12	0.37
23	3 Test Stands	VOC	0.12	0.37

APPENDIX D

Field Data

PRELIMINARY SURVEY DATA SHEET NO. 2

(Velocity and Temperature Traverse)

BASE	DATE		
Kelly AFB	19 Jul 75		
BOILER NUMBER	Source Inlet Duct to Fuel Accessory Shop's SUE Incinerator (Run #1)		
INSIDE STACK DIAMETER Area	5' by 2' = 10 ft ² <small>inches</small>		
STATION PRESSURE	29,260 In Hg		
STACK STATIC PRESSURE	-1.46 In H2O		
SAMPLING TEAM	AL/DEBQ		
TRaverse Point Number	Velocity Head, V_p in H2O	$\sqrt{V_p}$	Stack Temperature, (°F) Dry Bulk Wet Bulk
1	0.050		87 72
2	0.080		85 69
3	0.078		83 69
4	0.040		85 69
5	0.080		85 70
6	0.102		78 68
7	0.105		77 67
8	0.100		83 69
9	0.102		77 69
10	0.115		83 73
11	0.100		78 69
12	0.100		83 69
13	0.150		82 70
14	0.130		80 69
15	0.139		81 70
16	0.141		82 71
Arg DP = 0.10		Arg = 82	70
Arg FPM = 18			
Arg FPM = 1,086	ACFM = 10,858		T. H ₂ O = 2.1
	DSLFM = 10,094		
AVERAGE			

PRELIMINARY SURVEY DATA SHEET NO. 2
 (Velocity and Temperature Traverse)

BASE	DATE		
Kelly AFB	20 Jul 75		
BOILER NUMBER	Inlet Duct to Fuel Accessory Shells & Incinerator (Run #2)		
INSIDE STACK DIAMETER	5' by 2' = 10 ft ² <small>inches</small>		
STATION PRESSURE	29.205 In Hg		
STACK STATIC PRESSURE	-1.46 In H2O		
SAMPLING TEAM	AL/0EBQ		
TRaverse Point Number	Velocity Head, V _p in H2O	$\sqrt{V_p}$	Stack Temperature (°F) Dry Bulb Wet Bulb
1	0.045		81° 72°
2	0.065		79° 69°
3	0.075		79° 69°
4	0.025		79° 70°
5	0.100		83° 71°
6	0.115		79° 70°
7	0.110		79° 70°
8	0.090		79° 69°
9	0.115		81° 70°
10	0.105		80° 70°
11	0.110		80° 69°
12	0.090		80° 69°
13	0.175		84° 71°
14	0.135		82° 70°
15	0.140		80° 69°
16	0.155		80° 69°
	Avg ΔP = 0.10	Avg = 80 "	70
Avg FPM = 18	ACFM = 10,901	9. H ₂ O = 2.2	
Avg FPM = 1,090	DSCFM = 10,132		
AVERAGE			

PRELIMINARY SURVEY DATA SHEET NO. 2
(Velocity and Temperature Traverse)

BASE	DATE		
KELLY AFB	20 JU 95		
BOILER NUMBER	Inlet Duct to Fuel Accessory Stoves SUE Incinerator (Run #3)		
INSIDE STACK DIAMETER Area	5' by 2' = 10 ft ²	Inches	
STATION PRESSURE	29.205	In Hg	
STACK STATIC PRESSURE	-1.46	In H20	
SAMPLING TEAM	AL/OEBQ		
TRaverse Point Number	Velocity Head, V_p in H20	$\sqrt{V_p}$	Stack Temperature (°F) DRY BULR WET BULR
1	0.030		86° 72°
2	0.055		83° 69°
3	0.055		85° 71°
4	0.040		82° 69°
5	0.110		89° 70°
6	0.115		84° 69°
7	0.105		83° 69°
8	0.095		84° 70°
9	0.090		85° 70°
10	0.120		84° 69°
11	0.115		84° 69°
12	0.095		84° 69°
13	0.135		82° 70°
14	0.145		84° 69°
15	0.165		84° 69°
16	0.160		86° 69°
	Avg ΔP = 0.10	Avg =	84 70
Avg FPS = 18			
Avg FPM = 1,085	A CFM = 10,841	g. H ₂ O = 2.0	
	A SCFM = 10,028		
	AVERAGE		

VOC Emissions Data Sheet

Base: Kelly AFB Date: 19 Jul 95
 Source: Inlet duct to Fuel Accessory Shpr's Run #: 1
SUE Incinerator

Calibration Data: (Note - meter readings must be within \pm 5% of actual gas concentrations)

	Gas Concentration (ppm)	Meter Reading (ppm)	Mil Time
High Span:	803	803	1241
Medium Span:	506	500	1244
Low Span:	251	250	1247

Sampling Data:

<i>STO</i> Military Time	Reading (ppm)	<i>STO</i> Military Time	Reading (ppm)
12:56	182	1:30 pm	192
12:57	185	1:31 pm	191
12:58	193	1:32 pm	209
12:59 AM	198	1:33 pm	214
1:00 PM	192	1:34	218
1:01	222	1:35	219
1:02	208	1:36	215
1:03	224	1:37	213
1:04	224	1:38	209
1:05	214	1:39	199
1:06	212	1:40	196
1:07	218	1:41	194
1:08	237	1:42	190
1:09	228	1:43	186
1:10	228	1:44	186
1:11	240	1:45	189
1:12	237	1:46	183
1:13	238	1:47	182
1:14	231	1:48	183
1:15	230	1:49	180
1:16	226	1:50	177
1:17	220	1:51	172
1:18	218	1:52	173
1:19	211	1:53	171
1:20	212	1:54	166
1:21	206	1:55	171
1:22	204	1:56	167
1:23	201		
1:24	199		
1:25	195		
1:26	193		
1:27	193		
1:28	192		
1:29	191	Average Reading (ppm) =	202

$$240 \text{ ppm} - 191 \text{ ppm} = 49 \text{ ppm}$$

VOC Emissions Data Sheet

Base: *Kelly AFB*

Source: *Inlet Duct to Fuel Accessory Ship's
SUE Incinerator*

Date: *20 Jul 95*

Run #: *2*

Calibration Data: (Note - meter readings must be within $\pm 5\%$ of actual gas concentrations)

	Gas Concentration (ppm)	Meter Reading (ppm)	Time
High Span:	803	803	1006
Medium Span:	506	501	1008
Low Span:	251	251	1010

Sampling Data:

Time	Reading (ppm)	Time	Reading (ppm)
1042	112	1116	88
1043	111	1117	87
1044	109	1118	87
1045	111	1119	84
1046	110	1120	84
1047	110	1121	87
1048	108	1122	94
1049	106	1123	94
1050	105	1124	94
1051	104	1125	94
1052	104	1126	94
1053	103	1127	95
1054	102	1128	98
1055	100	1129	101
1056	99	1130	120
1057	98	1131	117
1058	96	1132	118
1059	95	1133	118
1100	97	1134	116
1101	97	1135	112
1102	95	1136	114
1103	94	1137	112
1104	95	1138	115
1105	93	1139	110
1106	94	1140	110
1107	92	1141	108
1108	90	1142	113
1109	91		
1110	91		
1111	90		
1112	90		
1113	91		
1114	89		
1115	88	Average Reading (ppm) =	100

VOC Emissions Data Sheet

Base: K6114 4FB Date: 20 Jul 95
 Source: Inlet Duct to Fuel Accessory shop's Run #: 3
 SNC Incinerator

Calibration Data: (Note - meter readings must be within \pm 5% of actual gas concentrations)

	Gas Concentration (ppm)	Meter Reading (ppm)	Time
High Span:	803	803	1309
Medium Span:	506	500	1311
Low Span:	251	251	1313

Sampling Data:

Time	Reading (ppm)	Time	Reading (ppm)
1327	135	1401	132
1328	135	1402	133
1329	136	1403	132
1330	148	1404	131
1331	144	1405	129
1332	147	1406	128
1333	148	1407	129
1334	152	1418	150
1335	155	1409	158
1336	170	1410	151
1337	167	1411	149
1338	165	1412	156
1329	163	1413	150
1340	162	1414	145
1341	160	1415	142
1342	156	1416	140
1343	155	1417	136
1344	152	1418	135
1345	153	1419	134
1346	150	1420	138
1347	148	1421	130
1348	145	1422	130
1349	144	1423	127
1350	143	1424	139
1351	148	1425	136
1352	153	1426	134
1353	149	1427	131
1354	147		
1355	144		
1356	140		
1357	138		
1358	139		
1359	134		
1400	133	Average Reading (ppm) =	144

PRELIMINARY SURVEY DATA SHEET NO. 1
(Stack Geometry)

PRELIMINARY SURVEY DATA SHEET NO. 2
 (Velocity and Temperature Traverse)

BASE <i>Kelly AFB</i>	DATE <i>8 Jan 95</i>	Start time 1444	
BOILER NUMBER <i>SUE Incinerator</i>	Bldg 348		
INSIDE STACK DIAMETER <i>Triangular stack with Effective diameter of 28.05 inches, Area of 8 ft</i>			
STATION PRESSURE <i>29.625</i>	In Hg		
STACK STATIC PRESSURE <i>-0.20</i>	In H2O		
SAMPLING TEAM			
TRaverse Point Number	Velocity Head, V_p in H2O	✓ ✓ Cyclonic angle	Stack Temperature (°F)
1	0.301	17	620
2	0.317	17	626
3	0.265	14	627
4	0.215	15	626
5	0.155	7	625
6	0.115	3	619
7	0.100	0	616
8	0.418	24	619
9	0.308	19	622
10	0.180	12	620
11	0.140	9	617
12	0.135	9	614
13	0.430	14	606
14	0.350	8	616
15	0.230	0	617
16	0.360	0	597
AVERAGE	57		

Particulate Sampling Data Sheet

Schematic of Stack									
Top Level 15" Hg at 15 "Hg Pre Train Check: OK									
Pre Train Check: OK (at 15 "Hg)									
Post Train Check: OK (at 2 "Hg)									
Assumptions									
Nozzle Diameter: 0.347	in Pre Pilot Check: OK								
Base: Kel 1/4	Pilot Coefficient, C_p : 0.84	Post Pilot Check: OK							
Source ID: UE Internor	Meter Box Yr: 1, 031	Pre Train Check: OK	(at 15 "Hg)						
Run Number: 1	Meter Box $\Delta H@$: 1.144	Post Train Check: OK	(at 2 "Hg)						
Station Pressure: 29.305 "Hg	Meter Box #: 6	%H ₂ O: 8	MW _D : 2.9	Sample Box Temp (°F): 245	Sample Box Temp (°F): 240	Probe Temp (°F): 240	Impinger Temp (°F): 242	Outlet Temp (°F): 242	Vacuum Pressure ("Hg): 2.5
Static Pressure: -0.1 "H ₂ O	Probe #: 601	%H ₂ O: 8							
Traverse Point Number	Sampling Time (min)	Dry Gas Meter Vol (ft ³)	Gas Meter Temp, T _m (°F)	Stack Temp, T _s (°F)	Velocity Head, Δp ("H ₂ O)	Orifice Diff Press, ΔH ("H ₂ O)	Probe Temp (°F)	Sample Box Temp (°F)	Impinger Temp (°F)
1	3.75	188.053	73	74	0.355	1.7	239	245	240
2	7.50	78	74	609	0.350	1.7	240	240	240
3	11.25	81	75	610	0.260	1.7	241	242	242
4	15.00	83	76	611	0.210	1.7	241	242	242
5	18.75	86	77	609	0.175	1.7	242	243	243
6	22.50	89	78	605	0.145	1.7	243	244	244
7	26.25	89	78	602	0.115	1.7	244	244	244
8	30.00	88	78	609	0.412	1.7	241	242	242
9	33.75	89	79	610	0.273	1.7	241	242	242
10	37.50	90	79	611	0.157	1.7	241	242	242
11	41.25	91	80	611	0.138	1.7	242	242	242
12	45.00	92	80	611	0.160	1.7	242	242	242
13	48.75	89	80	600	0.461	1.7	241	243	243
14	52.50	91	81	607	0.360	1.7	242	242	242
15	56.25	92	81	608	0.225	1.7	242	242	242
16	60.00	90	82	577	0.430	1.7	242	241	241

Total Gas Vol = **42.082** Avg T_m = **83** Avg ΔH = **6.06**

Meter Box Operator: **R. O'Brien**

Avg (P_sT_s)^{0.5} =

Avg ΔH =

Signature: **Ronald O'Brien**

Nov 95

Particulate Sampling Data Sheet

Schematic of Stack									
# 5 10 11 12 13 14 15 16 17 18					Top View 1. 10 2. 11 3. 12 4. 13 5. 14 6. 15 7. 16 8. 17 9. 18 10. 19 11. 20 12. 21 13. 22 14. 23 15. 24 16. 25 17. 26 18. 27 19. 28 20. 29 21. 30 22. 31 23. 32 24. 33 25. 34 26. 35 27. 36 28. 37 29. 38 30. 39 31. 40 32. 41 33. 42 34. 43 35. 44 36. 45 37. 46 38. 47 39. 48 40. 49 41. 50 42. 51 43. 52 44. 53 45. 54 46. 55 47. 56 48. 57 49. 58 50. 59 51. 60 52. 61 53. 62 54. 63 55. 64 56. 65 57. 66 58. 67 59. 68 60. 69 61. 70 62. 71 63. 72 64. 73 65. 74 66. 75 67. 76 68. 77 69. 78 70. 79 71. 80 72. 81 73. 82 74. 83 75. 84 76. 85 77. 86 78. 87 79. 88 80. 89 81. 90 82. 91 83. 92 84. 93 85. 94 86. 95 87. 96 88. 97 89. 98 90. 99 91. 100 92. 101 93. 102 94. 103 95. 104 96. 105 97. 106 98. 107 99. 108 100. 109 101. 110 102. 111 103. 112 104. 113 105. 114 106. 115 107. 116 108. 117 109. 118 110. 119 111. 120 112. 121 113. 122 114. 123 115. 124 116. 125 117. 126 118. 127 119. 128 120. 129 121. 130 122. 131 123. 132 124. 133 125. 134 126. 135 127. 136 128. 137 129. 138 130. 139 131. 140 132. 141 133. 142 134. 143 135. 144 136. 145 137. 146 138. 147 139. 148 140. 149 141. 150 142. 151 143. 152 144. 153 145. 154 146. 155 147. 156 148. 157 149. 158 150. 159 151. 160 152. 161 153. 162 154. 163 155. 164 156. 165 157. 166 158. 167 159. 168 160. 169 161. 170 162. 171 163. 172 164. 173 165. 174 166. 175 167. 176 168. 177 169. 178 170. 179 171. 180 172. 181 173. 182 174. 183 175. 184 176. 185 177. 186 178. 187 179. 188 180. 189 181. 190 182. 191 183. 192 184. 193 185. 194 186. 195 187. 196 188. 197 189. 198 190. 199 191. 200 192. 201 193. 202 194. 203 195. 204 196. 205 197. 206 198. 207 199. 208 200. 209 201. 210 202. 211 203. 212 204. 213 205. 214 206. 215 207. 216 208. 217 209. 218 210. 219 211. 220 212. 221 213. 222 214. 223 215. 224 216. 225 217. 226 218. 227 219. 228 220. 229 221. 220 222. 221 223. 222 224. 223 225. 224 226. 225 227. 226 228. 227 229. 228 230. 229 231. 230 232. 231 233. 232 234. 233 235. 234 236. 235 237. 236 238. 237 239. 238 240. 239 241. 240 242. 241 243. 242 244. 243 245. 244 246. 245 247. 246 248. 247 249. 248 250. 249 251. 250 252. 251 253. 252 254. 253 255. 254 256. 255 257. 256 258. 257 259. 258 260. 259 261. 260 262. 261 263. 262 264. 263 265. 264 266. 265 267. 266 268. 267 269. 268 270. 269 271. 270 272. 271 273. 272 274. 273 275. 274 276. 275 277. 276 278. 277 279. 278 280. 279 281. 280 282. 281 283. 282 284. 283 285. 284 286. 285 287. 286 288. 287 289. 288 290. 289 291. 290 292. 291 293. 292 294. 293 295. 294 296. 295 297. 296 298. 297 299. 298 300. 299 301. 300 302. 301 303. 302 304. 303 305. 304 306. 305 307. 306 308. 307 309. 308 310. 309 311. 310 312. 311 313. 312 314. 313 315. 314 316. 315 317. 316 318. 317 319. 318 320. 319 321. 320 322. 321 323. 322 324. 323 325. 324 326. 325 327. 326 328. 327 329. 328 330. 329 331. 330 332. 331 333. 332 334. 333 335. 334 336. 335 337. 336 338. 337 339. 338 340. 339 341. 340 342. 341 343. 342 344. 343 345. 344 346. 345 347. 346 348. 347 349. 348 350. 349 351. 350 352. 351 353. 352 354. 353 355. 354 356. 355 357. 356 358. 357 359. 358 360. 359 361. 360 362. 361 363. 362 364. 363 365. 364 366. 365 367. 366 368. 367 369. 368 370. 369 371. 370 372. 371 373. 372 374. 373 375. 374 376. 375 377. 376 378. 377 379. 378 380. 379 381. 380 382. 381 383. 382 384. 383 385. 384 386. 385 387. 386 388. 387 389. 388 390. 389 391. 390 392. 391 393. 392 394. 393 395. 394 396. 395 397. 396 398. 397 399. 398 400. 399 401. 400 402. 401 403. 402 404. 403 405. 404 406. 405 407. 406 408. 407 409. 408 410. 409 411. 410 412. 411 413. 412 414. 413 415. 414 416. 415 417. 416 418. 417 419. 418 420. 419 421. 420 422. 421 423. 422 424. 423 425. 424 426. 425 427. 426 428. 427 429. 428 430. 429 431. 430 432. 431 433. 432 434. 433 435. 434 436. 435 437. 436 438. 437 439. 438 440. 439 441. 440 442. 441 443. 442 444. 443 445. 444 446. 445 447. 446 448. 447 449. 448 450. 449 451. 450 452. 451 453. 452 454. 453 455. 454 456. 455 457. 456 458. 457 459. 458 460. 459 461. 460 462. 461 463. 462 464. 463 465. 464 466. 465 467. 466 468. 467 469. 468 470. 469 471. 470 472. 471 473. 472 474. 473 475. 474 476. 475 477. 476 478. 477 479. 478 480. 479 481. 480 482. 481 483. 482 484. 483 485. 484 486. 485 487. 486 488. 487 489. 488 490. 489 491. 490 492. 491 493. 492 494. 493 495. 494 496. 495 497. 496 498. 497 499. 498 500. 499 501. 500 502. 501 503. 502 504. 503 505. 504 506. 505 507. 506 508. 507 509. 508 510. 509 511. 510 512. 511 513. 512 514. 513 515. 514 516. 515 517. 516 518. 517 519. 518 520. 519 521. 520 522. 521 523. 522 524. 523 525. 524 526. 525 527. 526 528. 527 529. 528 530. 529 531. 530 532. 531 533. 532 534. 533 535. 534 536. 535 537. 536 538. 537 539. 538 540. 539 541. 540 542. 541 543. 542 544. 543 545. 544 546. 545 547. 546 548. 547 549. 548 550. 549 551. 550 552. 551 553. 552 554. 553 555. 554 556. 555 557. 556 558. 557 559. 558 560. 559 561. 560 562. 561 563. 562 564. 563 565. 564 566. 565 567. 566 568. 567 569. 568 570. 569 571. 570 572. 571 573. 572 574. 573 575. 574 576. 575 577. 576 578. 577 579. 578 580. 579 581. 580 582. 581 583. 582 584. 583 585. 584 586. 585 587. 586 588. 587 589. 588 590. 589 591. 590 592. 591 593. 592 594. 593 595. 594 596. 595 597. 596 598. 597 599. 598 600. 599 601. 600 602. 601 603. 602 604. 603 605. 604 606. 605 607. 606 608. 607 609. 608 610. 609 611. 610 612. 611 613. 612 614. 613 615. 614 616. 615 617. 616 618. 617 619. 618 620. 619 621. 620 622. 621 623. 622 624. 623 625. 624 626. 625 627. 626 628. 627 629. 628 630. 629 631. 630 632. 631 633. 632 634. 633 635. 634 636. 635 637. 636 638. 637 639. 638 640. 639 641. 640 642. 641 643. 642 644. 643 645. 644 646. 645 647. 646 648. 647 649. 648 650. 649 651. 650 652. 651 653. 652 654. 653 655. 654 656. 655 657. 656 658. 657 659. 658 660. 659 661. 660 662. 661 663. 662 664. 663 665. 664 666. 665 667. 666 668. 667 669. 668 670. 669 671. 670 672. 671 673. 672 674. 673 675. 674 676. 675 677. 676 678. 677 679. 678 680. 679 681. 680 682. 681 683. 682 684. 683 685. 684 686. 685 687. 686 688. 687 689. 688 690. 689 691. 690 692. 691 693. 692 694. 693 695. 694 696. 695 697. 696 698. 697 699. 698 700. 699 701. 700 702. 701 703. 702 704. 703 705. 704 706. 705 707. 706 708. 707 709. 708 710. 709 711. 710 712. 711 713. 712 714. 713 715. 714 716. 715 717. 716 718. 717 719. 718 720. 719 721. 720 722. 721 723. 722 724. 723 725. 724 726. 725 727. 726 728. 727 729. 728 730. 729 731. 730 732. 731 733. 732 734. 733 735. 734 736. 735 737. 736 738. 737 739. 738 740. 739 741. 740 742. 741 743. 742 744. 743 745. 744 746. 745 747. 746 748. 747 749. 748 750. 749 751. 750 752. 751 753. 752 754. 753 755. 754 756. 755 757. 756 758. 757 759. 758 760. 759 761. 760 762. 761 763. 762 764. 763 765. 764 766. 765 767. 766 768. 767 769. 768 770. 769 771. 770 772. 771 773. 772 774. 773 775. 774 776. 775 777. 776 778. 777 779. 778 780. 779 781. 780 782. 781 783. 782 784. 783 785. 784 786. 785 787. 786 788. 787 789. 788 790. 789 791. 790 792. 791 793. 792 794. 793 795. 794 796. 795 797. 796 798. 797 799. 798 800. 799 801. 800 802. 801 803. 802 804. 803 805. 804 806. 805 807. 806 808. 807 809. 808 810. 809 811. 810 812. 811 813. 812 814. 813 815. 814 816. 815 817. 816 818. 817 819. 818 820. 819 821. 820 822. 821 823. 822 824. 823 825. 824 826. 825 827. 826 828. 827 829. 828 830. 829 831. 830 832. 831 833. 832 834. 833 835. 834 836. 835 837. 836 838. 837 839. 838 840. 839 841. 840 842. 841 843. 842 844. 843 845. 844 846. 845 847. 846 848. 847 849. 848 850. 849 851. 850 852. 851 853. 852 854. 853 855. 854 856. 855 857. 856 858. 857 859. 858 860. 859 861. 860 862. 861 863. 862 864. 863 865. 864 866. 865 867. 866 868. 867 869. 868 870. 869 871. 870 872. 871 873. 872 874. 873 875. 874 876. 875 877. 876 878. 877 879. 878 880. 879 881. 880 882. 881 883. 882 884. 883 885. 884 886. 885 887. 886 888. 887 889. 888 890. 889 891. 890 892. 891 893. 892 894. 893 895. 894 896. 895 897. 896 898. 897 899. 898 900. 899 901. 900 902. 901 903. 902 904. 903 905. 904 906. 905 907. 906 908. 907 909. 908 910. 909 911. 910 912. 911 913. 912 914. 913 915. 914 916. 915 917. 916 918. 917 919. 918 920. 919 921. 920 922. 921 923. 922 924. 923 925. 924 926. 925 927. 926 928. 927 929. 928 930. 929 931. 930 932. 931 933. 932 934. 933 935. 934 936. 935 937. 936 938. 937 939. 938 940. 939 941. 940 942. 941 943. 942 944. 943 945. 944 946. 945 947. 946 948. 947 949. 948 950. 949 951. 950 952. 951 953. 952 954. 953 955. 954 956. 955 957. 956 958. 957 959. 958 960. 959 961. 960 962. 961 963. 962 964. 963 965. 964 966. 965 967. 966 968. 967 969. 968 970. 969 971. 970 972. 971 973. 972 974. 973 975. 974 976. 975 977. 976 978. 977 979. 978 980. 979 981. 980 982. 981 983. 982 984. 983 985. 984 986. 985 987. 986 988. 987 989. 988 990. 989 991. 990 992. 991 993. 992 994. 993 995. 994 996. 995 997. 996 998. 997 999. 998 1000. 999 1001. 1000 1002. 1001 1003. 1002 1004. 1003 1005. 1004 1006. 1005 1007. 1006 1008. 1007 1009. 1008 1010. 1009 1011. 1010 1012. 1011 1013. 1012 1014. 1013 1015. 1014 1016. 1015 1017. 1016 1018. 1017 1019. 1018 1020. 1019 1021. 1020 1022. 1021 1023. 1022 1024. 1023 1025. 1024 1026. 1025 1027. 1026 1028. 1027 1029. 1028 1030. 1029 1031. 1030 1032. 1031 1033. 1032 1034. 1033 1035. 1034 1036. 1035 1037. 1036 1038. 1037 1039. 1038 1040. 1039 1041. 1040 1042. 1041 1043. 1042 1044. 1043 1045. 1044 1046. 1045 1047. 1046 1048. 1047 1049. 1048 1050. 1049 1051. 1050 1052. 1051 1053. 1052 1054. 1053 1055. 1054 1056. 1055 1057. 1056 1058. 1057 1059. 1058 1060. 1059 1061. 1060 1062. 1061 1063. 1062 1064. 1063 1065. 1064 1066. 1065 1067. 1066 1068. 1067 1069. 1068 1070. 1069 1071. 1070 1072. 1071 1073. 1072 1074. 1073 1075. 1074 1076. 1075 1077. 1076 1078. 1077 1079. 1078 1080. 1079 1081. 1080 1082. 1081 1083. 1082 1084. 1083 1085. 1084 1086. 1085 1087. 1086 1088. 1087 1089. 1088 1090. 1089 1091. 1090 1092. 1091 1093. 10				

Sampled 11/11/96



Particulate Sampling Data Sheet

Traverse Point Number	Sampling Time (min)	Dry Gas Meter Vol (ft ³)	Gas Meter Temp, T _m (°F)	Stack Temp, T _s (°F)	Velocity Head, Δp ("H ₂ O)	Orifice Press, ΔH ("H ₂ O)	Probe Temp (°F)	Sample Box Temp (°F)	Impinger Temp (°F)	Assumptions		Schematic of Stack
										%H ₂ O:	MWB:	
0	273.327	77	78	633	0.340	1.7	241	245	58			
1	3.75	84	79	639	0.355	1.7	241	242	51			
2	7.50	86	79	638	0.270	1.7	241	244	53			
3	11.25	88	79	644	0.240	1.7	242	244	54			
4	15.00	89	79	640	0.195	1.7	242	242	55			
5	18.75	89	80	634	0.150	1.7	240	242	55			
6	22.50	90	80	630	0.125	1.7	233	243	56			
7	26.25	91	80	630	0.125	1.7	233	243	56			
8	30.00	87	80	631	0.415	1.7	240	244	57			
9	33.75	89	80	633	0.280	1.7	243	243	53			
10	37.50	90	80	635	0.178	1.7	241	243	51			
11	41.25	91	80	635	0.132	1.7	243	242	52			
12	45.00	91	80	635	0.170	1.7	242	242	51			
13	48.75	86	80	619	0.445	1.7	241	242	53			
14	52.50	90	80	635	0.368	1.7	242	242	51			
15	56.25	90	80	633	0.250	1.7	243	241	51			
16	60.00	87	80	557	0.419	1.7	241	241	56			
		315,755										
Total Gas Vol = 42,428		Avg T _m = 84	Avg T _s = 129	Avg ΔH =								
Meter Box Vol = 4.0												
Signature: R. J. Brien												

Nov 95

Total Gas Vol = 42,428 Avg T_m = 84 Avg T_s = 129 Avg ΔH =

Signature: R. J. Brien



Signature: R. J. Brien

AIR POLLUTION PARTICULATE ANALYTICAL DATA

BASE Kelly AFB	DATE 10 JUN 76	RUN NUMBER 1			
BUILDING NUMBER 348	SOURCE NUMBER SUE Incinerator				
I. PARTICULATES					
ITEM	FINAL WEIGHT (gm)	INITIAL WEIGHT (gm)	WEIGHT PARTICLES (gm)		
FILTER NUMBER					
ACETONE WASHINGS (Probe, Front Half Filter)					
BACK HALF (if needed)					
	Total Weight of Particulates Collected		gm		
II. WATER					
ITEM	FINAL WEIGHT (gm)	INITIAL WEIGHT (gm)	WEIGHT WATER (gm)		
IMPINGER 1 (H ₂ O)	216	200	16		
IMPINGER 2 (H ₂ O)	204	200	4		
IMPINGER 3 (Dry)	0	0	0		
IMPINGER 4 (Silica Gel)	206 gm	200	6		
	Total Weight of Water Collected		26 gm		
III. GASES (Dry)					
ITEM	ANALYSIS 1	ANALYSIS 2	ANALYSIS 3	ANALYSIS 4	AVERAGE
VOL % CO ₂					
VOL % O ₂					
VOL % CO					
VOL % N ₂					
Vol % N ₂ = (100% - % CO ₂ - % O ₂ - % CO)					

AIR POLLUTION PARTICULATE ANALYTICAL DATA

BASE Kelly AFB	DATE 11 JUN 96	RUN NUMBER 2			
BUILDING NUMBER 348	SOURCE NUMBER SUE Incinerator				
I. PARTICULATES					
ITEM	FINAL WEIGHT (gm)	INITIAL WEIGHT (gm)	WEIGHT PARTICLES (gm)		
FILTER NUMBER					
ACETONE WASHINGS (Probe, Front Half Filter)					
BACK HALF (if needed)					
	Total Weight of Particulates Collected		gm		
II. WATER					
ITEM	FINAL WEIGHT (gm)	INITIAL WEIGHT (gm)	WEIGHT WATER (gm)		
IMPIINGER 1 (H ₂ O)	207	200	7		
IMPIINGER 2 (H ₂ O)	200	200	0		
IMPIINGER 3 (D ₂ O)	0	0	0		
IMPIINGER 4 (Silica Gel)	208	200	8		
	Total Weight of Water Collected		15 gm		
III. GASES (Dry)					
ITEM	ANALYSIS 1	ANALYSIS 2	ANALYSIS 3	ANALYSIS 4	AVERAGE
VOL % CO ₂					
VOL % O ₂					
VOL % CO					
VOL % N ₂					
Vol % N ₂ = (100% - % CO ₂ - % O ₂ - % CO)					

AIR POLLUTION PARTICULATE ANALYTICAL DATA

BASE Kelly AFB	DATE 11 Jan 96	RUN NUMBER 3			
BUILDING NUMBER 348	SOURCE NUMBER SUE Incinerator				
I. PARTICULATES					
ITEM	FINAL WEIGHT (gm)	INITIAL WEIGHT (gm)	WEIGHT PARTICLES (gm)		
FILTER NUMBER					
ACETONE WASHINGS (Probe, Front Half Filter)					
BACK HALF (If needed)					
	Total Weight of Particulates Collected		gm		
II. WATER					
ITEM	FINAL WEIGHT (gm)	INITIAL WEIGHT (gm)	WEIGHT WATER (gm)		
IMPIINGER 1 (H ₂ O)	212	200	12		
IMPIINGER 2 (H ₂ O)	200	200	0		
IMPIINGER 3 (D ₂ O)	0	0	0		
IMPIINGER 4 (Silica Gel)	207	200	7		
	Total Weight of Water Collected		gm		
III. GASES (Dry)					
ITEM	ANALYSIS 1	ANALYSIS 2	ANALYSIS 3	ANALYSIS 4	AVERAGE
VOL % CO ₂					
VOL % O ₂					
VOL % CO					
VOL % N ₂					
Vol % N ₂ = (100% - % CO ₂ - % O ₂ - % CO)					

VISIBLE EMISSION OBSERVATION FORM

SOURCE NAME Fuel & Accessories Repair & Test Facility Incinerator		OBSERVATION DATE 10 JAN 96				START TIME 1200 CST		STOP TIME 1230 CST			
ADDRESS		SEC M	0	15	30	45	SEC M	0	15	30	45
CITY Kelly AFB	STATE TX	ZIP	1	0 0	0 0	0 0	31				
PHONE	SOURCE ID NUMBER		2	0 0	0 0	0 0	32				
PROCESS EQUIPMENT Thermal Oxidizer		OPERATING MODE 70%		3	0 0	0 0	0 0	33			
CONTROL EQUIPMENT Allen Bradley PLC-5		OPERATING MODE Automatic		4	0 0	0 0	0 0	34			
DESCRIBE EMISSION POINT tan brick stack located within the walled/fenced area on the north side of bldg 348 (FART Building)				5	0 0	0 0	0 0	35			
HEIGHT ABOVE GROUND LEVEL 30'	HEIGHT RELATIVE TO OBSERVER 30'	6	0 0	0 0	0 0	0 0	36				
DISTANCE FROM OBSERVER 250'	DIRECTION FROM OBSERVER 320°	7	0 0	0 0	0 0	0 0	37				
DESCRIBE EMISSIONS plume shape not visually detectable				8	0 0	0 0	0 0	38			
EMISSION COLOR Clear	PLUME TYPE: CONTINUOUS <input checked="" type="checkbox"/> FUGITIVE <input type="checkbox"/> INTERMITTENT <input type="checkbox"/>	9	0 0	0 0	0 0	0 0	39				
WATER DROPLETS PRESENT NO <input checked="" type="checkbox"/> YES <input type="checkbox"/>	IS WATER DROPLET PLUME ATTACHED <input type="checkbox"/> DETACHED <input type="checkbox"/>	10	0 0	0 0	0 0	0 0	40				
AT WHAT POINT IN THE PLUME WAS OPACITY DETERMINED just above stack tip				11	0 0	0 0	0 0	41			
DESCRIBE BACKGROUND blue sky with scattered white cirrus clouds				12	0 0	0 0	0 0	42			
BACKGROUND COLOR Blue	SKY CONDITIONS mostly clear (scattered high cirrus clouds)	13	0 0	0 0	0 0	0 0	43				
WIND SPEED 5 KTS	WIND DIRECTION E 150°	14	0 0	0 0	0 0	0 0	44				
AMBIENT TEMPERATURE 64°F	RELATIVE HUMIDITY 62%	15	0 0	0 0	0 0	0 0	45				
SOURCE LAYOUT SKETCH				16	0 0	0 0	0 0	46			
				17	0 0	0 0	0 0	47			
				18	0 0	0 0	0 0	48			
				19	0 0	0 0	0 0	49			
				20	0 0	0 0	0 0	50			
				21	0 0	0 0	0 0	51			
				22	0 0	0 0	0 0	52			
				23	0 0	0 0	0 0	53			
				24	0 0	0 0	0 0	54			
				25	0 0	0 0	0 0	55			
				26	0 0	0 0	0 0	56			
				27	0 0	0 0	0 0	57			
				28	0 0	0 0	0 0	58			
				29	0 0	0 0	0 0	59			
				30	0 0	0 0	0 0	60			
AVERAGE OPACITY FOR HIGHEST PERIOD				NUMBER OF READINGS ABOVE 0				% WERE			

COMMENTS	RANGE OF OPACITY READINGS 0 MINIMUM : 0 MAXIMUM			
OBSERVER'S NAME (PRINT) THOMAS C. MOORE				
OBSERVER'S SIGNATURE Thomas C. Moore		DATE 10 Jan 96		
ORGANIZATION U.S. Air Force (AL/0 EBA)				
I HAVE RECEIVED A COPY OF THESE OPACITY OBSERVATIONS SIGNATURE		CERTIFIED BY Philip J. Clark (TNRCC)		
TITLE		DATE 15 Sep 95		

VISIBLE EMISSION OBSERVATION FORUM

SOURCE NAME USAF Fuel Accessories Repair & Test Facility Incinerator		
ADDRESS		
CITY Kelly AFB	STATE TX	ZIP
PHONE	SOURCE ID NUMBER	
PROCESS EQUIPMENT Thermal Oxidizer	OPERATING MODE 70%	
CONTROL EQUIPMENT Allen Bradley PLC-5	OPERATING MODE Automatic	
DESCRIBE EMISSION POINT (square stack with triangular inside) tan brick incinerator stack located in fenced/walled area on north side of bldg		
HEIGHT ABOVE GROUND LEVEL 30'	HEIGHT RELATIVE TO OBSERVER 30'	
DISTANCE FROM OBSERVER 250'	DIRECTION FROM OBSERVER 320°	
DESCRIBE EMISSIONS Emission/plume characteristics not visually detectable		
EMISSION COLOR clear	PLUME TYPE: <input checked="" type="checkbox"/> CONTINUOUS <input type="checkbox"/> FUGITIVE <input type="checkbox"/> INTERMITTENT	
WATER DROPLETS PRESENT NO	IS WATER DROPLET PLUME ATTACHED <input type="checkbox"/> DETACHED <input checked="" type="checkbox"/>	
AT WHAT POINT IN THE PLUME WAS OPACITY DETERMINED just above stack tip (6")		
DESCRIBE BACKGROUND clear sky w/some light haze in distance		
BACKGROUND COLOR light blue sky	SKY CONDITIONS clear w/some haze along horizon	
WIND SPEED 16 KTS	WIND DIRECTION E 360	
AMBIENT TEMPERATURE 63°	RELATIVE HUMIDITY 31% (SP=29,460)	
SOURCE LAYOUT/SKETCH 		
COMMENTS		
I HAVE RECEIVED A COPY OF THESE OPACITY OBSERVATIONS		
SIGNATURE	TITLE	
	DATE	

AVERAGE OPACTITY FOR HIGHEST PERIOD 0	NUMBER OF READINGS ABOVE % WERE
RANGE OF OPACTITY READINGS 0 MINIMUM 0 MAXIMUM	
OBSERVER'S NAME (PRINT) THOMAS C. MOORE	
OBSERVER'S SIGNATURE Thomas C. More	DATE 11 Jan 96
ORGANIZATION USAF	(AL/0EBQ) Brooks AFB TX)
CERTIFIED BY	DATE

CERTIFIED BY		DATE
Philip J. Clark (TAKCC)		15 Sep 95
VERIFIED BY		DATE
5		*

VISIBLE EMISSION OBSERVATION FORM

SOURCE NAME USAF Fuel Accessories Repair & Test Facility Incinerator		OBSERVATION DATE 11 Jan 95				START TIME 1:45 CST		STOP TIME 7:15 CST			
ADDRESS		sec M	0	15	30	45	sec M	0	15	30	45
CITY Kelly AFB		STATE TX	ZIP	1	0	0	0	0	31		
PHONE		SOURCE ID NUMBER		2	0	0	0	0	32		
PROCESS EQUIPMENT Thermal Oxidizer		OPERATING MODE 70%		3	0	0	0	0	33		
CONTROL EQUIPMENT Allen Bradley PLC -5		OPERATING MODE Automatic		4	0	0	0	0	34		
DESCRIBE EMISSION POINT (Square Stack with triangular inside, tan brick incinerator stack located in fenced/wooded area on north side)				5	0	0	0	0	35		
HEIGHT ABOVE GROUND LEVEL 30'		HEIGHT RELATIVE OF BLDG 34B TO OBSERVER 30'		6	0	0	0	0	36		
DISTANCE FROM OBSERVER 250'		DIRECTION FROM OBSERVER 320°		7	0	0	0	0	37		
DESCRIBE EMISSIONS emission/plume characteristics not visually detectable				8	0	0	0	0	38		
EMISSION COLOR clean		PLUME TYPE: CONTINUOUS <input checked="" type="checkbox"/> FUGITIVE <input type="checkbox"/> INTERMITTENT <input type="checkbox"/>		9	0	0	0	0	39		
WATER DROPLETS PRESENT NO <input checked="" type="checkbox"/> YES <input type="checkbox"/>		IS WATER DROPLET PLUME ATTACHED <input type="checkbox"/> DETACHED <input type="checkbox"/>		10	0	0	0	0	40		
AT WHAT POINT IN THE PLUME WAS OPACITY DETERMINED just above stack tip (6")				11	0	0	0	0	41		
DESCRIBE BACKGROUND clear sky				12	0	0	0	0	42		
BACKGROUND COLOR Blue Sky		SKY CONDITIONS CLR		13	0	0	0	0	43		
WIND SPEED 15 KTS		WIND DIRECTION E 340		14	0	0	0	0	44		
AMBIENT TEMPERATURE 68°		RELATIVE HUMIDITY 14% 29.410		15	0	0	0	0	45		
				16	0	0	0	0	46		
				17	0	0	0	0	47		
				18	0	0	0	0	48		
				19	0	0	0	0	49		
				20	0	0	0	0	50		
				21	0	0	0	0	51		
				22	0	0	0	0	52		
				23	0	0	0	0	53		
				24	0	0	0	0	54		
				25	0	0	0	0	55		
				26	0	0	0	0	56		
				27	0	0	0	0	57		
				28	0	0	0	0	58		
				29	0	0	0	0	59		
				30	0	0	0	0	60		
AVERAGE OPACITY FOR HIGHEST PERIOD				NUMBER OF READINGS ABOVE % WERE							
COMMENTS				RANGE OF OPACITY READINGS MINIMUM : MAXIMUM							
				OBSERVER'S NAME (PRINT) THOMAS C. MOORE							
				OBSERVER'S SIGNATURE Thomas C. Moore				DATE 11 Jan 96			
				ORGANIZATION USAF (AC/06BQ, Brooks AFB TX)							
I HAVE RECEIVED A COPY OF THESE OPACITY OBSERVATIONS				CERTIFIED BY Philip J. Clark (TNAcc)				DATE 15 Sep 95			
SIGNATURE		DATE		VERIFIED BY				DATE			
TITLE											

ENERAC Field Data Sheet

Base: Kelly AFB Date: 10 JAN
 Source: SUE Incinerator
 Run #: 1
 Fuel Type:
 Recorder's Name: JAG

Calibration Information: 5A 31000106 Model 3000 Cal'd by: the JAGMAN

Date/Time Analyzer was last zeroed: 10 JAN 1/332

Date/Time Analyzer was last calibrated: 9 JAN 1/2259


Sampling Data: (Note - readings should be taken at 2-minute intervals)

Time	O ₂ (%)	CO (ppm)	SO ₂ (ppm)	CO ₂ (%)	NO (ppm)	NO ₂ (ppm)	NO _X (ppm)	Comments
1416	18.8	95	3	1.6	25	0	25	↑
18	18.8	93	3	1.6	25	0	1	
20	18.8	94	3	1.6	25	0	1	
22	18.8	93	3	1.6	25	0	1	
24	18.8	95	0	1.6	25	0	1	
26	18.8	97	0	1.6	25	0	1	
28	18.8	97	0	1.6	25	0	1	
30	18.8	97	3	1.6	25	0	1	
32	18.8	9.3	0	1.6	25	0	1	
34	18.8	90	3	1.6	25	0	1	
36	18.8	90	3	1.6	25	0	1	
38	18.8	88	3	1.6	25	0	1	
40	18.8	90	3	1.6	25	0	1	
42	18.8	91	3	1.6	25	0	1	
44	18.8	88	3	1.6	25	0	1	
46	18.8	90	3	1.6	25	0	1	Good Job
48	18.8	90	3	1.6	25	0	1	
50	18.8	90	3	1.6	27	0	1	
52	18.9	90	3	1.6	27	0	1	
54	18.8	89	3	1.6	27	0	1	
56	18.8	89	3	1.6	27	0	1	
58	18.9	88	3	1.6	27	0	1	
1500	18.9	90	3	1.6	27	0	1	
02	18.9	90	3	1.5	27	0	1	
04	18.9	88	3	1.5	27	0	1	
06	18.9	87	3	1.5	25	0	1	
08	18.9	90	3	1.5	25	0	1	
10	18.9	90	3	1.5	26	0	1	
12	18.9	88	3	1.6	27	0	1	
14	18.9	86	3	1.5	27	0	1	
16	18.9	83	3	1.5	27	0	1	↓
Average =	18.8	91	3	1.6	26	0		

Nov 95

Operator: KURT D. JAGIELSKI, MSgt, USAF
 Superintendent, Air Quality and
 Hazardous Waste Branch

Signature:



ENERAC Field Data Sheet

Base: KELLY Date: 11 JAN 96

Source: SUEZ incinerator

Run #: 2

Fuel Type:

Recorder's Name: JAG

Calibration Information:

Date/Time Analyzer was last zeroed: 11 JAN / 1139

Date/Time Analyzer was last calibrated: 9 JAN / 2259

Sampling Data: (Note - readings should be taken at 2-minute intervals)

Time	O ₂ (%)	CO (ppm)	SO ₂ (ppm)	CO ₂ (%)	NO (ppm)	NO ₂ (ppm)	NO _x (ppm)	Comments
1155	18.7	133	0	1.7	25	0		
57	19.7	128	0	1.7	25	0		
59	18.6	121	0	1.8	28	0		
1201	18.4	116	0	1.9	34	0		
03	18.5	114	0	1.8	29	0		
05	18.7	118	0	1.7	27	0		
07	18.7	115	0	1.7	27	0		
09	18.7	111	0	1.7	27	0		
11	18.6	107	0	1.8	31	0		
13	18.4	100	0	1.9	35	1	0	
15	18.6	102	0	1.7	28	0		
17	18.7	104	0	1.6	27	0		
19	18.7	104	0	1.6	27	0		
21	18.8	102	0	1.6	27	0		
23	18.6	97	0	1.8	31	0		
25	18.4	93	0	1.9	36	1	0	
27	18.7	97	0	1.7	28	0		
29	18.8	104	0	1.6	27	0		
31	18.8	102	0	1.6	27	0		
33	18.8	104	0	1.6	28	0		
35	18.6	102	0	1.7	31	0		
37	18.5	106	0	1.8	35	1	0	
39	18.5	109	0	1.8	35	0		
41	18.7	110	0	1.6	28	0		
43	18.8	113	0	1.6	27	0		
45	18.8	112	0	1.6	27	0		
47	18.8	109	0	1.6	27	0		
49	18.8	106	0	1.6	27	0		
51	18.8	106	0	1.6	27	0		
53	18.8	106	0	1.6	27	0		
55	18.7	106	0	1.7	30	0		
Average =	18.7	108	0	1.7	29	0		

Nov 95

Operator: KURT D. JAGIELSKI, MSgt, USAF
Superintendent, Air Quality and
Hazardous Waste Branch

68

Signature: KD Jag

ENERAC Field Data Sheet

Base: KELLY Date: 11 JAN 96

Source: SUE Incinerator

Run #: 3

Fuel Type:

Recorder's Name: JAG

Calibration Information:

Date/Time Analyzer was last zeroed: 11 JAN/1426

Date/Time Analyzer was last calibrated: 9 JAN / 2259

Sampling Data: (Note - readings should be taken at 2-minute intervals)

Time	O ₂ (%)	CO (ppm)	SO ₂ (ppm)	CO ₂ (%)	NO (ppm)	NO ₂ (ppm)	NO _x (ppm)	Comments
1442	18.8	62	0	1.6	32	0	0	
44	18.8	60	0	1.6	33	0	0	
46	19.0	62	0	1.5	28	0	0	
48	19.0	62	0	1.5	27	0	0	
50	18.8	60	0	1.6	31	0	0	
52	18.6	53	0	1.7	38	0	0	
54	18.6	51	0	1.7	38	0	0	
56	18.9	59	0	1.5	28	0	0	
58	19.0	58	0	1.5	28	0	0	
1500	19.0	58	0	1.5	27	0	0	
02	19.0	57	0	1.5	27	0	0	
04	18.9	58	0	1.5	29	0	0	
06	18.7	53	0	1.6	31	0	0	
08	18.8	53	0	1.6	33	0	0	
10	18.8	53	0	1.6	34	0	0	
12	18.7	48	0	1.7	36	0	0	
14	19.0	53	0	1.5	28	0	0	
16	18.9	53	0	1.5	28	0	0	
18	18.9	53	0	1.6	32	0	0	
20	18.8	51	0	1.5	30	0	0	
22	18.8	53	0	1.6	32	0	0	
24	18.8	53	0	1.6	32	0	0	
26	18.9	51	0	1.6	32	0	0	
28	18.8	51	0	1.6	33	0	0	
30	18.8	42	0	1.6	33	0	0	
32	18.8	49	0	1.6	31	0	0	
34	19.0	53	0	1.5	28	0	0	
36	18.8	50	0	1.6	33	0	0	
38	18.8	48	0	1.6	33	0	0	
40	19.0	51	0	1.5	27	0	0	
42	18.8	48	0	1.6	31	0	0	
Average =	18.8	54	0	1.6	31	0	0	

Nov 95

Operator: KURT D. JAGIELSKI, MSgt, USAF
Superintendent, Air Quality and
Hazardous Waste Branch

Signature: K. D. Jagielski

VOC Emissions Data Sheet

Base: KELLY AFB Date: 10 JAN 96
 Source: INCINERATOR Run #: 1

Calibration Data: (Note - meter readings should be within \pm 5% of actual gas concentrations)

	Gas Concentration (ppm)	Meter Reading (ppm)	Time
74-4	Zero:	0	1307
6-4	High Span:	88.2	1312
	Mid Span:	49.1	1314
	Low Span:	24.4	1316

System bias check using High Span Gas: 85.0

Sampling Data: (Note - readings should be taken at 1-minute intervals)

Time	Reading (ppm)	Comments	Time	Reading (ppm)	Comments
14:16	16.4		14:48	14.2	
:17	16.0		49	14.2	
18	15.4		50	14.2	
19	15.4		51	13.6	
20	17.0		52	14.6	
21	16.1		53	14.1	
22	15.6		54	13.9	
23	15.9		55	13.7	
24	17.3		56	13.7	
25	17.8		57	13.2	
26	18.0		58	13.5	
27	19.0		14:59	13.5	↓
28	19.9		15:00	13.2	INCINERATOR TEMP UP
29	19.1		15:01	13.0	INCREASED BY 5°
14:30	17.8		02	13.0	DURING PFR 60 SO DECREASE
31	17.9	TEMP	03	12.6	IN READINGS SHOULD BE
32	16.4	DECAY	04	12.7	OBSERVED
33	15.5		05	12.6	Fuel rate also increased
34	15.4		06	12.5	from 107 to 109 ppm
35	14.9		07	13.4	
36	15.4		08	13.3	
37	14.3		09	12.9	
38	15.4		10	12.9	
39	15.3		11	12.9	
40	16.2		12	12.6	
41	15.6		13	12.8	
42	15.6		14	12.8	
43	14.9		15	12.6	
44	14.8		16	13.0	
45	14.8		17	13.2	
46	14.6	↓	18	12.7	
14:47	14.0		19	13.2	
			Average = 14.7		

Nov 95

Operator: LT KYLE BLASH

Signature: Kyle Blash

VOC Emissions Data Sheet

Base: KELLY AFB
Source: INCINERATOR

Date: 11 JAN 96
Run #: 2

Calibration Data: (Note - meter readings should be within \pm 5% of actual gas concentrations)

	Gas Concentration (ppm)	Meter Reading (ppm)	Time
Zero:	0	0	10:32
High Span:	80.2	80.2	10:40
Mid Span:	49.6	49.6	10:45
Low Span:	24.4	25.0	10:51
SYSTEM BIAS CHECK	80.0	81.1	11:26

Sampling Data: (Note - readings should be taken at 1-minute intervals)

Time	Reading (ppm)	Comments	Time	Reading (ppm)	Comments
11:55	13.1		12:27	6.8	
11:56	12.3		12:28	7.5	
11:57	10.9		29	7.8	
11:58	10.7		30	7.6	
11:59	10.1		31	7.8	
12:00	9.0		32	8.7	
:01	8.8		33	8.7	
02	8.4		34	8.6	
03	8.5		35	8.4	
04	8.4		36	9.2	
05	8.8		37	9.2	
06	8.7		38	9.4	
07	8.8		39	8.9	
08	9.5		40	10.2	
09	8.1		41	10.7	
10	7.5		42	10.9	
11	7.4		43	11.1	
12	7.7		44	10.7	
13	7.3		45	10.8	
14	7.9		46	10.7	
15	6.9		47	10.6	
16	7.0		48	10.7	
17	7.3		49	10.8	
18	7.4		50	10.8	
19	7.6		51	10.9	
20	7.9		52	10.8	
21	7.7		53	11.4	
22	7.4		54	11.6	
23	7.2		55	11.1	
24	7.5		56	11.2	
25	7.5		57	10.7	
12:26	7.4		12:58	10.4	
			Average =	9.1	

Nov 95

Operator: KYLE BLANCH

Signature: Kyle Blanch

VOC Emissions Data Sheet

Base: KELLY AFB Date: 11 JAN 96
 Source: TNC-NEZATOR Run #: 3

Calibration Data: (Note - meter readings should be within \pm 5% of actual gas concentrations)

	Gas Concentration (ppm)	Meter Reading (ppm)	Time
Zero:	0	0	1346
High Span:	80.2	80.2	1350
Mid Span:	49.6	49.9	1353
Low Span:	24.4	24.9	1357

Sampling Data: (Note - readings should be taken at 1-minute intervals)

Time	Reading (ppm)	Comments	Time	Reading (ppm)	Comments
14:52	7.7		15:14	7.6	
43	7.7		15	7.3	
44	7.8		16	7.4	
45	7.9		17	7.9	
46	7.0		18	8.5	
47	7.4		19	9.5	
48	7.4		20	8.0	
49	7.3		21	8.2	
50	8.2		22	8.5	
51	8.6		23	8.0	
52	9.1		24	8.0	
53	9.2		25	7.8	
54	9.0		26	7.7	
55	7.2		27	8.0	
56	7.4		28	8.0	
57	7.5		29	8.0	
58	7.3		30	7.8	
59	7.8		31	7.9	
15:00	7.6		32	7.8	
01	8.0		33	7.3	
02	8.2		34	7.6	
03	9.1		35	7.7	
04	9.1		36	8.3	
05	9.8		37	8.0	
06	8.6		38	8.1	
07	8.9		39	7.4	
08	8.8		40	7.6	
09	8.5		41	8.6	
10	9.0		42	7.8	
11	9.0		43	8.0	
12	8.8		44	8.4	
15:13	7.0		15:45	7.6	
			Average =	8.1	

Nov 95

Operator: KYLE BLASCH

Signature: Kyle A. Blasch

• St. Maure 1/11/96

Calibration Fluid Consumption During
Emissions Testing of SUE Incinerator

Sample Run #	Initial Fluid Reading (lb)	End Fluid Reading (lb)	Fuel Consumed (lb)	Initial Fluid Flow Rate Reading (pph)	End Fluid Flow Rate Reading (pph)	Average Fluid Flow Rate Reading (pph)
1	Not Recorded	Not Recorded	—	67	107	108
2	Not Recorded	Not Recorded	—	107.5	107.2	107
3	19194	19307	108	108.1	107.5	108


Incinerator Burner Temperatures During
Emissions Testing of SUE Incinerator

Sample Run #	Set Burner Temperature (°F)	Initial Burner Temperature (°F)	End Burner Temperature (°F)	Average Burner Temperature (°F)
1	1470	Not Recorded	Not Recorded	—
2	1512	1510	1524	1515
3	1515	1520	1520	1520

Sampling Date/Time

Run #1: 10 Jun 96 1416 - 1516 hrs
 Run #2: 11 Jun 96 1155 - 1255 hrs
 Run #3: 11 Jun 96 1442 - 1542 hrs

SUE Incinerator Temperature Chart During Exhaust Stack Sampling



APPENDIX E
Calibration Data

METER BOX CALIBRATION DATA AND CALCULATION FORM

(English units)

Date 7 June 95Meter box number 6Barometric pressure, $P_b = 28.990$ in. Hg Calibrated by Dobbins / JAG

Orifice manometer setting (ΔH), in. H_2O	Gas volume		Temperatures				Time (θ), min	Y_i	$\Delta H@_i$ in. H_2O	
	Wet test meter (V_w), ft ³	Dry gas meter (V_d), ft ³	Wet test meter (t_w), °F	Dry gas meter inlet (t_d), °F	Outlet (t_d), °F	Avg (t_d), °F				
5	0.5	5	4.99	72	79.5	74.5	77	12.85	1.010	1.903
5	1.0	5	4.98	72	86	77	82	9.13	1.020	1.904
5.5	1.5	10	9.995	72	91.5	80.5	86	15.24	1.023	1.975
5.0	2.0	10	10.05	72	98	85	92	13.23	1.027	1.963
6.0	3.0	10	10.075	72	102	87.5	95	10.81	1.028	1.955
6.5	4.0	10	10.085	72	104	88.5	96	9.39	1.026	1.963
								Avg	1.022	1.944

ΔH , in. H_2O	$\frac{\Delta H}{13.6}$	$Y_i = \frac{V_w P_b (t_d + 460)}{V_d (P_b + \frac{\Delta H}{13.6}) (t_w + 460)}$	$\Delta H@_i = \frac{0.0317 \Delta H}{P_b (t_d + 460)} \left[\frac{(t_w + 460) \theta}{V_w} \right]^2$
0.5	0.0368	$5 \times 28.99 (77+460)$ $4.99 (28.99 + 0.5/13.6) (72+460)$	$0.0317 (0.5)$ $28.99 (77+460)$
1.0	0.0737	$5 \times 28.99 (82+460)$ $4.98 (28.99 + 1.0/13.6) (72+460)$	$0.0317 (1)$ $28.99 (82+460)$
1.5	0.110	$10 \times 28.99 (86+460)$ $9.995 (28.99 + 1.5/13.6) (72+460)$	$0.0317 (1.5)$ $28.99 (86+460)$
2.0	0.147	$10 \times 28.99 (92+460)$ $10.05 (28.99 + 2/13.6) (72+460)$	$0.0317 (2)$ $28.99 (92+460)$
3.0	0.221	$10 \times 28.99 (95+460)$ $10.075 (28.99 + 3/13.6) (72+460)$	$0.0317 (3)$ $28.99 (95+460)$
4.0	0.294	$10 \times 28.99 (96+460)$ $10.085 (28.99 + 4/13.6) (72+460)$	$0.0317 (4)$ $28.99 (96+460)$

^a If there is only one thermometer on the dry gas meter, record the temperature under t_d .

NOZZLE CALIBRATION DATA FORM

Kelly AFB Exhaust sampling of SUE Incinerator

Date 9 Jan 76Calibrated by R. O'Brien

Nozzle identification number	Nozzle Diameter ^a			ΔD , ^b mm (in.)	D_{avg} ^c
	D_1 , mm (in.)	D_2 , mm (in.)	D_3 , mm (in.)		
28	0.346	0.347	0.347	0.001	0.347

where:

^a $D_{1,2,3}$ = three different nozzles diameters, mm (in.); each diameter must be within (0.025 mm) 0.001 in.

^b ΔD = maximum difference between any two diameters, mm (in.),
 $\Delta D \leq (0.10 \text{ mm}) 0.004 \text{ in.}$

^c D_{avg} = average of D_1 , D_2 , and D_3 .

TYPE S PITOT TUBE INSPECTION DATA FORM

1 Apr 93

Pitot tube assembly level? yes _____ noPitot tube openings damaged? _____ yes (explain below) no $\alpha_1 = \underline{1}^\circ$ ($<10^\circ$), $\alpha_2 = \underline{2}^\circ$ ($<10^\circ$), $\beta_1 = \underline{1.5}^\circ$ ($<5^\circ$), $\beta_2 = \underline{1.5}^\circ$ ($<5^\circ$) $\gamma = \underline{0}^\circ$, $\theta = \underline{1.0}^\circ$, $A = \underline{(0.866)}$ cm (in.) $z = A \sin \gamma = \underline{0}$ cm (in.); < 0.32 cm ($< 1/8$ in.) $w = A \sin \theta = \underline{(0.015)}$ cm (in.); $< .08$ cm ($< 1/32$ in.) $P_A = \underline{(0.433)}$ cm (in.) $P_B = \underline{(0.433)}$ cm (in.) $D_t = \underline{(0.372)}$ cm (in.)Comments: calibrated by O'Brien and JagielskiCalibration required? _____ yes no

STACK TEMPERATURE SENSOR CALIBRATION DATA FORM

Date 2 Apr 93 Thermocouple number 6-1Ambient temperature 22.2 °C Barometric pressure 29.280 in. HgCalibrator O'Brien/
Jagielski Reference: mercury-in-glass ASTM 3F

other

Reference point number ^a	Source ^b (specify)	Reference thermometer temperature, °C	Thermocouple potentiometer temperature, °C	Temperature difference, % ^c
0	Ice water	0.0	1.1	0.40
100	Boiling water	99.1	100.6	0.38
—	Heated corn oil	298.9	304.4	0.96

^aEvery 30°C (50°F) for each reference point.^bType of calibration system used.^c
$$\left[\frac{(\text{ref temp, } ^\circ\text{C} + 273) - (\text{test thermom temp, } ^\circ\text{C} + 273)}{\text{ref temp, } ^\circ\text{C} + 273} \right] 100 \leq 1.5\%.$$

APPENDIX F
HP 41 Program Printouts

HP 41 "METH 4" Program Printouts for Exhaust Stack Sampling Runs 1, 2, & 3

Kelly AFB
Incinerator Testing
Run 1 10 Jan 96

METER BOX Y?	XROM "METH 4"
	1.0220 RUN
DELTA H?	1.7000 RUN
BAR PRESS ?	29.3050 RUN
METER VOL ?	42.0220 RUN
MTR TEMP F?	83.0000 RUN
% OTHER GAS	
REMOVED BEFORE	
DRY GAS METER ?	
STATIC HOH IN ?	-.2000 RUN
STACK TEMP.	606.0000 RUN
ML. WATER ?	26.0000 RUN

IMP. % HOH = 2.9
% HOH=2.9

Kelly AFB
Incinerator Testing
Run 2 11 Jan 96

METER BOX Y?	XROM "METH 4"
	1.0220 RUN
DELTA H?	1.7000 RUN
BAR PRESS ?	29.4600 RUN
METER VOL ?	42.3230 RUN
MTR TEMP F?	85.0000 RUN
% OTHER GAS	
REMOVED BEFORE	
DRY GAS METER ?	
STATIC HOH IN ?	-.2000 RUN
STACK TEMP.	632.0000 RUN
ML. WATER ?	15.0000 RUN

IMP. % HOH = 1.7
% HOH=1.7

Kelly AFB
Incinerator Testing
Run 3 11 Jan 96

METER BOX Y?	XROM "METH 4"
	1.0220 RUN
DELTA H?	1.7000 RUN
BAR PRESS ?	29.4100 RUN
METER VOL ?	42.4200 RUN
MTR TEMP F?	84.0000 RUN
% OTHER GAS	
REMOVED BEFORE	
DRY GAS METER ?	
STATIC HOH IN ?	-.2000 RUN
STACK TEMP.	629.0000 RUN
ML. WATER ?	19.0000 RUN

IMP. % HOH = 2.1
% HOH=2.1

HP 41 "METH 2" Program Printout for Exhaust Stack Sampling Run 1

XROM "METH 2"		
SITE ?		DELTA P 7. .115 RUN
KELLY AFB INCINERATOR		STACK TEMP? 602. RUN
STACK, RUN 1, 10 JAN 96		FPS = 27.
RUN.		
STACK DIA INCH?		DELTA P 8. .412 RUN
AREA SQ FT ?	8.0000	STACK TEMP? 609. RUN
NO TRAV PTS. ?	16.0000	FPS = 52.
BAR PRESS ?	29.3050	DELTA P 9. .275 RUN
STATIC IN HOH ?	.2000	STACK TEMP? 610. RUN
% MOISTURE ?	2.9000	FPS = 42.
PITOT CP ?	.8400	DELTA P 10. .151 RUN
% CO2 ?	1.6000	STACK TEMP? 611. RUN
% OXYGEN ?	18.6000	FPS = 32.
% CO ?		DELTA P 11. .128 RUN
MOL WT OTHER ?		STACK TEMP? 611. RUN
MWd = 29.01		
MW NET = 28.69		
RUN		
DELTA P 1. .355 RUN		DELTA P 12. .160 RUN
STACK TEMP? 603. RUN		STACK TEMP? 611. RUN
FPS = 48.		FPS = 32.
DELTA P 2. .350 RUN		DELTA P 13. .461 RUN
STACK TEMP? 609. RUN		STACK TEMP? 600. RUN
FPS = 48.		FPS = 55.
DELTA P 3. .263 RUN		DELTA P 14. .360 RUN
STACK TEMP? 610. RUN		STACK TEMP? 607. RUN
FPS = 41.		FPS = 49.
DELTA P 4. .210 RUN		DELTA P 15. .225 RUN
STACK TEMP? 611. RUN		STACK TEMP? 603. RUN
FPS = 37.		FPS = 36.
DELTA P 5. .175 RUN		DELTA P 16. .430 RUN
STACK TEMP? 609. RUN		STACK TEMP? 577. RUN
FPS = 34.		FPS = 52.
DELTA P 6. .145 RUN		AVE FPS = 41.
STACK TEMP? 605. RUN		AVE FPM = 2,430.
FPS = 31.		AVE DELTA P = 0.26
		STK PRS. ABS = 29.29
		AVE STK TEMP = 606.
		STACK ACFM = 19,440.
		DSCFM = 9,155.

HP 41 "METH 2" Program Printout for Exhaust Stack Sampling Run 2

XROM "METH 2"	DELTA P 7.	.125	RUN
SITE ?	STACK TEMP?	630.	RUN
KELLY AFB INCINERATOR	FPS = 29.		
STACK, RUN 3, 11 JAN 96			
RUN			
STACK DIA INCH?	DELTA P 8.	.415	RUN
AREA SQ FT ?	STACK TEMP?	631.	RUN
8.0000	FPS = 53.		
NO TRAV PTS. ?			
16.0000			
BAR PRESS ?	DELTA P 9.	.280	RUN
29.4100	STACK TEMP?	633.	RUN
STATIC IN HOH ?	FPS = 43.		
-.2000			
% MOISTURE ?	DELTA P 10.	.178	RUN
2.1000	STACK TEMP?	635.	RUN
PITOT CP ?	FPS = 34.		
.8400			
% CO2 ?	DELTA P 11.	.132	RUN
1.6000	STACK TEMP?	635.	RUN
% OXYGEN ?	FPS = 30.		
18.8000			
% CO ?	DELTA P 12.	.170	RUN
MOL WT OTHER ?	STACK TEMP?	635.	RUN
RUN	FPS = 34.		
MWD = 29.01			
MW WET = 28.78			
DELTA P 1.	DELTA P 13.	.445	RUN
STACK TEMP? .340	STACK TEMP?	619.	RUN
633.	FPS = 54.		
FPS = 48.			
DELTA P 2.	DELTA P 14.	.368	RUN
STACK TEMP? .355	STACK TEMP?	635.	RUN
639.	FPS = 50.		
FPS = 49.			
DELTA P 3.	DELTA P 15.	.250	RUN
STACK TEMP? .270	STACK TEMP?	633.	RUN
638.	FPS = 41.		
FPS = 43.			
DELTA P 4.	DELTA P 16.	.419	RUN
STACK TEMP? .240	STACK TEMP?	557.	RUN
641.	FPS = 51.		
FPS = 40.			
DELTA P 5.	AVE FPS = 42.		
STACK TEMP? .195	AVE FPM = 2,492.		
640.	AVE DELTA P = 0.27		
FPS = 36.	STK PRS. ABS = 29.40		
DELTA P 6.	AVE STK TEMP = 629.		
STACK TEMP? .150	STACK ACFM = 19,940.		
634.	DSCFM = 9,297.		
FPS = 32.			

HP 41 "METH 2" Program Printout for Exhaust Stack Sampling Run 3

SITE ?	XROM "METH 2"	DELTA P 7.	.113	RUN
KELLY AFB INCINERATOR		STACK TEMP?	632.	RUN
STACK, RUN 2, 11 JAN 96	RUN	FPS = 27.		
STACK DIA INCH?	RUN	DELTA P 8.	.416	RUN
AREA SQ FT ?	8.0000 RUN	STACK TEMP?	633.	RUN
NO TRAV PTS?	16.0000 RUN	FPS = 53.		
BAR PRESS ?	29.4600 RUN	DELTA P 9.	.265	RUN
STATIC IN HOH ?	.2000 RUN	STACK TEMP?	638.	RUN
% MOISTURE ?	1.7000 RUN	FPS = 44.		
PITOT CP ?	.8400 RUN	DELTA P 10.	.144	RUN
% CO2 ?	1.7000 RUN	STACK TEMP?	636.	RUN
% OXYGEN ?	18.7000 RUN	FPS = 31.		
% CO ?	RUN	DELTA P 11.	.120	RUN
MOL WT OTHER ?	RUN	STACK TEMP?	636.	RUN
MWD = 29.02		FPS = 28.		
MW WET = 28.83		DELTA P 12.	.155	RUN
DELTA P 1.	.340 RUN	STACK TEMP?	638.	RUN
STACK TEMP?	630. RUN	FPS = 32.		
FPS = 47.		DELTA P 13.	.410	RUN
DELTA P 2.	.350 RUN	STACK TEMP?	638.	RUN
STACK TEMP?	632. RUN	FPS = 52.		
FPS = 48.		DELTA P 14.	.348	RUN
DELTA P 3.	.265 RUN	STACK TEMP?	632.	RUN
STACK TEMP?	641. RUN	FPS = 48.		
FPS = 44.		DELTA P 15.	.210	RUN
DELTA P 4.	.225 RUN	STACK TEMP?	631.	RUN
STACK TEMP?	638. RUN	FPS = 37.		
FPS = 39.		DELTA P 16.	.436	RUN
DELTA P 5.	.185 RUN	STACK TEMP?	610.	RUN
STACK TEMP?	636. RUN	FPS = 53.		
FPS = 35.		AVE FPS = 41.		
DELTA P 6.	.135 RUN	AVE FPM = 2,431.		
STACK TEMP?	638. RUN	AVE DELTA P = 0.26		
FPS = 30.		STK PRS. ABS = 29.45		
		AVE STK TEMP = 632.		
		STACK ACFM = 19,446.		
		DSCFM = 9,097.		

HP 41 "WBDB" Program Printouts for Inlet Duct Sampling Runs 1, 2, & 3

Kelly AFB
Inlet Duct, Run 1
19 Jul 95

XROM "WBDB"
P BAR? 29.2600 RUN
STATIC HOH? -1.4600 RUN
DRY BULB TEMP? 82.0000 RUN
WET BULB TEMP? 70.0000 RUN
V.P. WET BULB? 0.7392 RUN
% HOH = 2.1

Kelly AFB
Inlet Duct, Run 2
20 Jul 95

XROM "WBDB"
P BAR? 29.2050 RUN
STATIC HOH? -1.4600 RUN
DRY BULB TEMP? 82.0000 RUN
WET BULB TEMP? 70.0000 RUN
V.P. WET BULB? 0.7392 RUN
% HOH = 2.2

Kelly AFB
Inlet Duct Run 3
20 Jul 95

XROM "WBDB"
P BAR? 29.2050 RUN
STATIC HOH? -1.4600 RUN
DRY BULB TEMP? 84.0000 RUN
WET BULB TEMP? 70.0000 RUN
V.P. WET BULB? 0.7392 RUN
% HOH = 2.0

HP 41 "METH 2" Program Printout for Inlet Duct Sampling Run 1

XROM "METH 2"			DELTA P 7.	.105	RUN
SITE ?	KELLY AFB	SUE INCINERATOR	STACK TEMP?	77.	RUN
INLET DUCT, RUN 1			FPS = 19.		
STACK DIA INCH?	RUN		DELTA P 8.	.10	RUN
AREA SQ FT ?	RUN		STACK TEMP?	83.	RUN
10.0000			FPS = 18.		
NO TRAV PTS. ?	RUN		DELTA P 9.	.102	RUN
16.0000			STACK TEMP?	77.	RUN
BAR PRESS ?	RUN		FPS = 18.		
29.2600			DELTA P 10.	.115	RUN
STATIC IN HCH ?	RUN		STACK TEMP?	83.	RUN
-1.4600			FPS = 20.		
% MOISTURE ?	RUN		DELTA P 11.	.10	RUN
2.1000			STACK TEMP?	78.	RUN
PITOT CP ?	RUN		FPS = 18.		
.8400			DELTA P 12.	.10	RUN
% CO2 ?	RUN		STACK TEMP?	83.	RUN
% OXYGEN ?	RUN		FPS = 18.		
20.9000			DELTA P 13.	.15	RUN
% CO ?	RUN		STACK TEMP?	82.	RUN
MOL WT OTHER ?	RUN		FPS = 22.		
MWD = 28.97			DELTA P 14.	.13	RUN
MW WET = 28.74			STACK TEMP?	80.	RUN
			FPS = 21.		
DELTA P 1.			DELTA P 15.	.139	RUN
STACK TEMP?	.05	RUN	STACK TEMP?	81.	RUN
FPS = 18.	87.		FPS = 22.		
DELTA P 2.			DELTA P 16.	.141	RUN
STACK TEMP?	.06	RUN	STACK TEMP?	82.	RUN
FPS = 16.	85.		FPS = 22.		
DELTA P 3.			AVE FPS = 18.		
STACK TEMP?	.078	RUN	AVE FPM = 1,086.		
FPS = 16.	83.		AVE DELTA P = 0.10		
DELTA P 4.			STK PRS. ABS = 29.15		
STACK TEMP?	.04	RUN	AVE STK TEMP = 82.		
FPS = 12.	85.		STACK ACFM = 10,658.		
DELTA P 5.			DSCFM = 10,094.		
STACK TEMP?	.06	RUN			
FPS = 16.	85.				
DELTA P 6.					
STACK TEMP?	.102	RUN			
FPS = 18.	78.				

HP 41 "METH 2" Program Printout for Inlet Duct Sampling Run 2

XROM "METH 2"			DELTA P 7.	.11	RUN
SITE ?	KELLY AFB	SUE INCINERATOR	STACK TEMP?	79.	RUN
INLET DUCT, RUN 2			FPS = 19.		
STACK DIA INCH?	RUN		DELTA P 8.	.09	RUN
AREA SQ FT ?	RUN		STACK TEMP?	79.	RUN
10.0000			FPS = 17.		
NO TRAV PTS. ?	RUN		DELTA P 9.	.115	RUN
16.0000			STACK TEMP?	81.	RUN
BAR PRESS ?	RUN		FPS = 20.		
29.2050			DELTA P 10.	.105	RUN
STATIC IN HOH ?	RUN		STACK TEMP?	80.	RUN
-1.4600			FPS = 19.		
% MOISTURE ?	RUN		DELTA P 11.	.11	RUN
2.2000			STACK TEMP?	80.	RUN
PITOT CP ?	RUN		FPS = 19.		
.6400			DELTA P 12.	.09	RUN
% CO2 ?	RUN		STACK TEMP?	80.	RUN
% OXYGEN ?	RUN		FPS = 17.		
20.9000			DELTA P 13.	.175	RUN
% CO ?	RUN		STACK TEMP?	84.	RUN
MOL WT OTHER ?	RUN		FPS = 24.		
MWD = 28.97			DELTA P 14.	.135	RUN
MW WET = 28.73			STACK TEMP?	82.	RUN
FPS = 12.			FPS = 21.		
DELTA P 1.	.045	RUN	DELTA P 15.	.14	RUN
STACK TEMP?	81.	RUN	STACK TEMP?	80.	RUN
FPS = 12.			FPS = 22.		
DELTA P 2.	.065	RUN	DELTA P 16.	.155	RUN
STACK TEMP?	79.	RUN	STACK TEMP?	80.	RUN
FPS = 15.			FPS = 23.		
DELTA P 3.	.075	RUN	AVE FPS = 18.		
STACK TEMP?	79.	RUN	AVE FPM = 1,090.		
FPS = 16.			AVE DELTA P = 0.10		
DELTA P 4.	.025	RUN	STK PRS. ABS = 29.10		
STACK TEMP?	79.	RUN	AVE STK TEMP = 80.		
FPS = 9.			STACK ACFM = 10,901.		
DELTA P 5.	.10	RUN	DSFCFM = 10,132.		
STACK TEMP?	83.	RUN			
FPS = 18.					
DELTA P 6.	.115	RUN			
STACK TEMP?	79.	RUN			
FPS = 20.					

HP 41 "METH 2" Program Printout for Inlet Duct Sampling Run 3

XROM "METH 2"				
SITE ?		DELTA P 7.	.125	RUN
KELLY AFB		STACK TEMP?	83.	RUN
SUE INCINERATOR		FPS = 19.		
INLET DUCT, RUN 3				
STACK DIA INCH?	RUN	DELTA P 8.	.095	RUN
AREA SQ FT ?	RUN	STACK TEMP?	84.	RUN
10.0000	RUN	FPS = 18.		
NO TRAV PTS?				
16.0000	RUN			
BAR PRESS ?		DELTA P 9.	.09	RUN
29.2950	RUN	STACK TEMP?	85.	RUN
STATIC IN HOH ?		FPS = 17.		
-1.4600	RUN			
% MOISTURE ?		DELTA P 10.	.12	RUN
2.0000	RUN	STACK TEMP?	84.	RUN
PITOT CP ?		FPS = 20.		
.8400	RUN			
% CO2 ?	RUN	DELTA P 11.	.115	RUN
% OXYGEN ?		STACK TEMP?	84.	RUN
20.9000	RUN	FPS = 20.		
% CO ?	RUN			
MOL WT OTHER ?	RUN			
MWd = 28.97				
MW WET = 28.75				
DELTA P 1.	.09	DELTA P 12.	.095	RUN
STACK TEMP?	86.	STACK TEMP?	84.	RUN
FPS = 18.		FPS = 18.		
DELTA P 2.	.055	DELTA P 13.	.135	RUN
STACK TEMP?	83.	STACK TEMP?	82.	RUN
FPS = 14.		FPS = 21.		
DELTA P 3.	.055	DELTA P 14.	.145	RUN
STACK TEMP?	85.	STACK TEMP?	84.	RUN
FPS = 14.		FPS = 22.		
DELTA P 4.	.04	DELTA P 15.	.165	RUN
STACK TEMP?	82.	STACK TEMP?	84.	RUN
FPS = 12.		FPS = 24.		
DELTA P 5.	.11	DELTA P 16.	.16	RUN
STACK TEMP?	89.	STACK TEMP?	86.	RUN
FPS = 19.		FPS = 26.		
DELTA P 6.	.115	Flow FPS = 18.		
STACK TEMP?	84.	Flow FPM = 1,085.		
FPS = 20.		Flow CPS = 0.10		
		Flow CFM = 13,647.		
		Flow SCFM = 10,026.		

APPENDIX G
VOC Analyzer Information

GENERAL DESCRIPTION


The J.U.M. Flame Ionization Analyzer Model 3-300A is an analyzer designed to continuously measure the concentration of total organic hydrocarbons in a gaseous sample. The sample can be ambient air, or the exhaust gases from a combustion process. This measurement is obtained by using the Flame Ionization Detector (FID).

The Model 3-300A is supplied in various versions through the use of options. The standard instrument has five Total Hydrocarbons measuring ranges: from 0-10 to 100,000 ppm with 10:1 Decade Range adjustment; Flame Out Indication of the front panel Dual Color LED (Red LED - Flame is Out, Green LED - Flame is Lit); 0-10 VDC Recorder Output, and two (2) internal calibration valves. Calibration gases are introduced into the analyzer using the rear panel zero gas and span gas inlet fittings. The standard 3-300A has a backpurge function for the built-in permanent stainless mesh sample filter. This sample filter backpurge function is activated by selecting PURGE via the front panel mode turn switch. An air line (max. pressure 90 psig) must be connected to the back of the 3-300A to manually backpurge the sample filter.



HEATED TOTAL HYDROCARBON ANALYZER

MODEL 3-300 A



The 3-300 A meets the requirements of EPA CFR 60, Method 25A, and EPA CFR, Method 503

The J.U.M. Engineering Model 3-300 A is a very compact, heated total hydrocarbon analyzer for high accuracy, sensitivity and stability.

The Model 3-300 A uses a hydrogen flame ionization detector (FID) in a heated oven to prevent the loss of high molecular weight hydrocarbons, and to provide reliable performance in the analysis of trace levels of contaminants in high purity gases, in air and in other gases.

The permanent sample filter is cleaned by backpurging and has a replaceable stainless mesh filter disc. A rear adapter plate allows quick installation of a heated sample line inside of the oven without the need for special tools.

Features

- 19 inch relay rack mount or table top case
- Precision 1% full scale
- Digital output display
- All heated components
- Adjustable oven temperature control up to 400 °F (204 °C)
- Permanent heated stainless steel 2 micron sample filter with replaceable disc
- Backpurge system allows filter to be cleaned without dismantling
- Fast response – within one second
- Automatic flame-out indicator with fuel shut-off valve
- Five selectable ranges can be gained by factor 10
- Automatic fuel enrichment for ignition
- Solenoid Valves for Sample, Zero Gas and Span Gas
- Remote control for sample, calibrate and backpurge is standard
- Automatic Sample Filter Backpurge (Option)

Applications

- Raw exhaust vehicle emissions
- Catalytic converter testing
- Detection of trace hydrocarbon levels in purity gases used in the semiconductor industry
- Monitors hydrocarbon contaminants in air and other gases
- Carbon adsorption regeneration control
- Measuring engine combustion efficiency
- LEL monitor of solvent-laden air
- Cryogenics/liquefaction
- Clean room applications
- Stack gas hydrocarbon emissions monitoring

Principle of Operation:

The Model 3-300 A uses the flame ionization detection (FID) method to determine the presence of total hydrocarbon concentrations in a gaseous sample.

Burning hydrocarbon free hydrogen in hydrocarbon free air produces a negligible number of ions. A hydrocarbon sample introduced into this flame starts a very complex ionization which creates a larger number of ions. A polarizing high voltage is applied between two electrodes around the burner jet and produces an electrostatic field. Now positive ions migrate to the collector electrode, and negative ions migrate to the high voltage electrode. The so generated ionization current between the two electrodes is directly proportional to the hydrocarbon concentration in the flame and is measured by the electrometer amplifier.

A sample pressure regulator provides a controlled back pressure at the sample capillary which gives admittance of a constant sample flow rate to the burner. This technique without the conventional sample back pressure regulator is used by J.U.M. Engineering since 20 years for highest sample flow rate stability and lowest maintenance. A compactly designed flow control module for the control of fuel and air flow rates via needle valve restrictors uses high precision pressure regulators. The needle valves are adjustable for easy optimization of the burner.


Options:

- 0-20 mA or 4-20 mA recorder output
- Adjustable 100 mVolt to 5 mVolt DC recorder output
- Remote range control
- Automatic range control


Standard specifications:

Analysis Method:	Flame Ionization Detector (FID)
Sensitivity:	Max.: 1 ppm CH ₄ full scale
Response Time:	90% of full scale in less than 1 second
Zero Drift:	1.5% of full scale per 24 hours
Span Drift:	1.5% of full scale per 24 hours
Linearity:	Within 1%
Oxygen Synergism:	Less than 1% of selected range
Ranges:	Any five of the following: 0-10, 100, 1000, 10,000, 100,000 ppm or 50, 100, 500, 1000, 5000, 10,000 or 0-100% LEL or other to be specified
Outputs:	0-10 Volts D.C. and 4-20 mA
Display:	Digital
Zero/Span Adjust:	Manual on front panel
Fuel Consumption:	Hydrogen: 20 cc min at 22 psig (1.5 Bar) 40% H ₂ /60% He: 80 cc min at 22 psig (1.5 Bar)
Analysis Temperature:	Adjustable 200 to 400 °F (93 to 204 °C)
Power Requirements:	110 Volts, 60 Hertz AC, 800 Watts 220 Volts, 50 Hertz AC, 800 Watts (other on request)
Ambient Temperature:	41 °F to 110 °F (5 to 43 °C)
Dimensions:	Width 483 mm (19 inch) Depth 460 mm (18 inch) Height 132 mm (5.19 inch)
Weight:	33 lbs (15 kg)

FLOW DIAGRAM



OUTLINE DIMENSIONS



J.U.M. Engineering Ges.m.b.H.: reserves the right, at any time and without notice, to change specifications presented within this data sheet, and assumes no responsibility for the application or use of devices herein described.

Warranty

J.U.M. Engineering Ges.m.b.H.: warrants each new unit of its manufacture to be free of defects in material and workmanship for one year from the date of delivery.

Made in Germany

© J.U.M. Engineering GmbH

J.U.M. Engineering Ges.m.b.H.
Liebigstraße 13
85757 Karlsfeld
Phone 011-49-8131-98795
Fax 011-49-8131-98894

Repr


Environmental Equipment Systems
5922 Portal Drive
Houston, TX 77096
Ph 713/723-0642
FAX 713/635-3004

Procedures Used for Calibrating VOC Analyzer

The VOC analyzer was calibrated (prior to each sample run) in the following manner:

- a. A zero gas (Pure Nitrogen) was introduced into the analyzer and the Zero Control adjusted so that the analyzer read zero.
- b. A high-level calibration gas, with a concentration equal to approximately 80% of the applicable analyzer span, was introduced into the analyzer and the Span Control adjusted so that the analyzer read the tagged value of the calibration gas.
- c. A mid-level calibration gas, with a concentration equal to approximately 50% of the applicable analyzer span, was then be introduced into the analyzer. The analyzer reading was compared to the tagged value of the calibration gas.
- d. A low-level calibration gas, with a concentration equal to approximately 25% of the applicable analyzer span, will next introduced into the analyzer. As with the mid-level gas, the analyzer reading was then compared to the tagged value.
- e. The analyzer was considered acceptable for testing if the readings obtained during the mid-level and low-level calibration gas checks were both within \pm 5% of the tagged value.

APPENDIX H
ENERAC 3000 Analyzer Information



ENERAC™ 3000SEM



ENERAC 3000SEM quality assured, compliance level emission analyzer provides a sound, cost-effective approach to establishing a complete, comprehensive and reliable emissions database. Advanced SEM™ sensor technology, Quality Assured/Precision Control Modules (QA/PCM), Integrated Sample Conditioning System, and documented Quality Assured/Calibration Certification Protocol (QA/CCP) provide positive assurance of instrument performance, and the generation of compliance-level NO, NO₂, NO_x, SO₂, and CO data.

The ENERAC 3000SEM provides facility operators a low cost, easy-to-implement capability to develop timely and representative data for CAAA requirements:

- NO_x RACT
- Operating Permits
- CEMS Back-up
- Enhanced Monitoring
- Audits
- Emission Rates



ENRAC 3000SEM Specifications

ICAL:

ASE: 18" x 13" x 6" Aluminum carrying case with ck. Weight: 22 lbs.
ROBE: 24" L x 3/8" OD. Inconel probe with astelloy X sintered filter and 1/2" deflector mounted on permeation drier housing. Probe housing connects to instrument via a 10 ft. Viton hose.
ax. continuous temperature: 1800 deg. F.
ax. sample dew point (past drier) 50 deg. F. @ 00 cc/min. (Natural gas fuel @ 0% oxygen).

TRICAL POWER:

ATTERY: 6V rechargeable, sealed lead-acid cell. three hour continuous battery operation. Quick 6 hour recharge.
2:120V/60 Hz. and 220V/50Hz standard.
C: 11-40 VDC/3A standard.

LAY:

5" High by 24 Character single line LCD with backlight illumination and adjustable viewing angle.

TER:

EIKO 4", 40 char. per line thermal printer with line feed button and with end of paper override. operates in any of four modes:
EXT MODE: 25 line printout of instant values of all measured parameters. (time req. 20 sec.)
LOT MODE: Any one parameter vs. time plotted. ordinate scales: full, half, quarter.
The scale: Selectable, 1 sec/dot-1 min/dot in 1 sec/dot intervals.
parameter plot CO-OXYGEN-NO_x-EFFICIENCY, single scale.

CALIBRATION CERTIFICATION

ROTOCOL (QA/CCP): Automatic printout of calibration test results, including sensor and filter performance status and diagnostics.

XTERNAL PRINT MODE: Prints messages sent via S-232 port.

RAGE:

ternal: 80 individually selectable buffers hold one complete set of measurements each in non volatile memory. Buffer contents can be sent to printer or S-232 port.

XTERNAL (OPTIONAL): Accessory pocket computer can store up to 300 measurements in non volatile memory.

UNICOMMUNICATIONS:

S-232 PORT: RS232c port (DTE), 1200 baud default, 300-9600 baud user selectable, half duplex, 1 start bit, 8 data bits, 1 stop bit, no parity.

ELEPHONE PORT: Internal 1200 baud modem connects to a modular phone line for remote communication.

FTWARE:

ENERCOM™ for Windows® software. 3.5" diskette, includes monitor, alarms, programming fuels, bar graphs and multiple time plots. Also available on DOS.

Complete package for SHARP 1600 pocket computer

ELLANEOUS:

UEL: 15 fuels, 3 in foreground, 12 in background standard. Custom fuels available on request.

CO ALARM: Selectable 0-2000 PPM in 10 ppm steps.

COMBUSTIBLES IN ASH: Presettable 0-100% in 5% steps.

MESSAGES: User friendly diagnostic and help messages.

CALIBRATION: Autogas span plus user selectable auto zero on start.

MEASURED PARAMETERS Range Resolution Accuracy

1. AMBIENT TEMPERATURE IC sensor. Degrees F or C	0-150° F 0-150° C	1° F or C	3° F
2. STACK TEMPERATURE Type K thermocouple Degrees F or C	0-2,000° F (-1,100° C)	1° F (1° C)	5° F
3. OXYGEN (O ₂) Electrochemical cell. Life 2 years	0-25%	0.1%	0.2%
4. SEM NITRIC OXIDE (NO) ■ Electrochemical cell. Life 2 years	0-1,000 PPM	1 PPM	2% of reading*
5. SEM NITROGEN DIOXIDE (NO ₂) ■ Electrochemical cell. Life 2 years	0-500 PPM**	1 PPM	2% of reading*
6. SEM CARBON MONOXIDE (CO) ■ Electrochemical cell. Life 2 years	0-2,000 PPM**	1 PPM	2% of reading*
7. SEM SULFUR DIOXIDE (SO ₂) ■ Electrochemical cell. Life 2 years	0-2,000 PPM**	1 PPM	2% of reading*
8. COMBUSTIBLES (GASES) Catalytic sensor. Life indefinite.	0-6%	0.01%	10% of reading in CH ₄ gas
9. SEM SINGLE, "DUAL RANGE" SENSOR ■ CARBON MONOXIDE (CO)	0-2,000 PPM [†] 0-20,000 PPM	1 PPM [†]	2% of reading**
10. SEM SINGLE, "DUAL RANGE" SENSOR ■ NITRIC OXIDE (NO)	0-1,000 PPM [†] 0-4,000 PPM	1 PPM [†]	2% of reading**
11. TIME/DATE	Time in hours, minutes, seconds. Date in month, day, year format.		

COMPUTED PARAMETERS Range Resolution Accuracy

1. COMBUSTION EFFICIENCY Heat loss method. Unique four loss factors computation (dry gas, water vapor, gaseous combustibles, combustibles in ash).	0-100%	0.1%	[4 loss]: 1% (above H ₂ O condensation) 2% (below H ₂ O condensation)
2. CARBON DIOXIDE (CO ₂)	0-40%	0.1%	5% of reading
3. EXCESS AIR	0-1000%	1%	10% of reading
4. OXIDES OF NITROGEN (NO _x)	0-1500 PPM**	1 PPM	2% of reading*
5. EMISSIONS 1. (CO, NO _x , SO ₂)	0-2500 milligrams/ cubic meter	2 mg/m ³	5% of reading*
6. EMISSIONS 2. (CO, NO _x , SO ₂) (Oxygen correction factor for emissions adjustable 0-20% in 1% steps plus TRUE).	0.000-9,999 lbs./ million BTU	0.001 lbs./ MMBTU	5% of reading*
7. EMISSIONS 3.	0-9.99 grams/ brake hp-hr	0.001 grms/ brake hp-hr	10% of reading*

* When tested according to 40 CFR 60, RAA test.

** Low range measurements.

** Other ranges available upon request.

Operational Flexibility

Historically, Clean Air Permits have been established using emission factors – half of these permits may be grossly understated, thus reducing long term operational flexibility. Many of the strategies being developed to provide future plant operational flexibility will rely on establishing accurate, defendable and cost-effective emissions data. ENERAC 3000SEM provides the most comprehensive and complete NO_x measurement available. Numerous independent studies have demonstrated ENERAC's ability to supply data that meets EPA enhanced monitoring performance requirements.

- Passed 40 CFR 60, Appendix B Performance Specification 2
- Passed NO_x Conversion Efficiency of Method 20, 40 CFR 60, App. A
- Passed Method 6C.5.1.5 and 7E Integrated Sample Conditioning requirements, 40 CFR 60, App. A
- Received Blue Ribbon Certificate of Verification from the Center for Emissions Research & Analysis

Operator Training & Certification

SEM electrochemical portable instrumentation is an important, cost-effective method to acquire compliance-level emission data. To ensure proper implementation, the operator should be trained as to the instrument's capabilities. ENERAC offers a Factory Training and Certification Program as proposed under 40 CFR 64 and detailed in the Enhanced Monitoring Reference document.

Remote Operation

2-way advanced communication and remote operation includes remote factory check and repair, and remote operation and reporting.

Accessories

A complete line of supporting accessories is available, and includes:

- Portable Gas Calibration Kit
- Dilution Kit for very high concentrations
- Computer Interfaced Software
- High Temperature Heat Shield
- SEM single, "Dual Range" Sensors CO and/or NO



1300 Shames Drive, Westbury, NY 11590
(516) 997-2100 • 1-800-695-3637 • Fax: (516) 997-2129



CHAPTER 1

FUNDAMENTALS

The ENERAC Model 3000 Integrated Emissions System is a portable state of the art analyzer designed for the following tasks:

- A. To measure the oxide of nitrogen emissions from stationary combustion sources in accordance with the EPA Provisional Reference Method (EMTIC CTM-022.WPF) for portable NOX analyzers.
- B. To measure the emissions of carbon monoxide, sulfur dioxide and gaseous combustibles and oxygen from stationary and mobile combustion sources.
- C. (OPTIONAL) To measure the stack gas velocity and volumetric flow rate and emission rates according to Method 2 Appendix A of 40CFR60.
- C. To assist the operator of a combustion source with the task of optimizing its performance and saving fuel.
- D. To be used as a management tool to assist the plant manager with keeping records and controlling costs.

The ENERAC Model 3000 is the most advanced instrument of its type. It uses the latest proprietary (SEM INSIDE (TM)) electrochemical sensor technology to measure emissions. To meet the accuracy requirements of the EPA reference methods each SEM sensor is supplied with three Precision Control Modules whose function is to select the measurement range (low, mid and high) that is appropriate for a particular measurement.

The ENERAC also uses the best available conditioning system technology (proprietary permeation drier configuration) for accurate transport of the sample gas to the instrument. It also uses sophisticated electronics and programming design for increased accuracy and flexibility. It measures 3 temperatures and 6 different stack gases. It computes efficiency of combustion as well as excess air

and carbon dioxide. In addition, it computes emissions in five different systems of units (ppm, milligrams/m³, lbs/MMBTU, grams/brake horsepower -hour and lbs / hour). It stores, prints and plots data. It communicates with a variety of other computers located near by via its RS-232 port, or remotely by telephone connection. It has a library of 15 fuels and over 100 diagnostic and help messages and can operate either on its rechargeable batteries, AC power, or from an external 6 Volt battery, or an 11-36 VDC (external battery system).

ENERGY EFFICIENCY SYSTEMS has years of experience in the manufacture and marketing of combustion and portable emission analyzers. The model 3000 is based on this experience, together with the latest innovations in electronic and sensor technology. It also expresses our basic conviction that communications and artificial intelligence are the basic ingredients of the instrument of the future.

The instrument operates basically as follows:

You select a sensor module (CO, NO and SO₂) whose range is appropriate to the measurement and set the Enerac for the chosen modules. You then insert the probe in the stack of an operating combustion source such as a boiler, furnace or combustion engine. A pump located inside the instrument draws a small sample of the stack gas. The sample is conditioned before entering the analyzer. A number of sensors analyze the contents of the stack gas and its temperature and calculate and display the results. The results can also be printed, stored or send to another computer either by direct connection or by the telephone lines. The source operator makes the required adjustments based on the analysis of the stack conditions to optimize performance.

A. UNPACKING THE INSTRUMENT

Every ENERAC model 3000 includes as standard equipment:

1. One Emissions Analyzer model 3000 (includes a roll of printer thermal paper).
2. One stack probe and permeation drier housing.
3. One 14" inconel probe extension and Hastelloy X sintered filter.

CHAPTER 11

CALIBRATION

Every instrument must occasionally be calibrated against some known value of a parameter in order to make sure that its accuracy has not deteriorated.

The instrument software make sure that the display readout is always a linear function of the source excitation (i.e. gas concentration or temperature etc.). You therefore need only two points on the straight line to calibrate a parameter over its entire range. Usually, the first point chosen is the zero value (called zeroing the instrument). The second point has to be set by using some known value of the parameter being calibrated (i.e. using for example 200 PPM certified carbon monoxide gas to set the display to read 200). Sometimes the second point is not needed, if the slope of the parameter is known and is always the same (for example for the stack temperature the slope of the curve is well known and you don't need a span calibration).

Traditionally, both zeroing and span (i.e. second point) calibration was done manually, by rotating suitable potentiometers until the display was set to read first zero in ambient air and then the correct value using span gas.

With the introduction of microprocessors, it became a simple matter for instruments to zero themselves automatically upon start up (AUTZERO), without having to use any adjustments. However, this simplification requires caution. The instrument must be started in a true "zero" environment. Otherwise it will assume as "zero" non zero conditions and give erroneous readings. (Example: Never autozero the ENERAC, if the probe tip is still hot following a recent measurement.)

The ENERAC carries out this improvement in automatic calibration procedure one step further. It does away with all potentiometric span adjustments. You just tell it the value of the calibrating parameter that you are using and the instrument adjusts itself automatically.

In addition, it carries out a systematic checkout of sensor performance and instrument integrity through a novel approach called the "ENERAC

CALIBRATION PROTOCOL". This protocol is explained below.

The ENERAC will "auto zero" itself every time you start the instrument, provided you push the ENTER key. Span calibration will be carried out on request.

You should carry out a span calibration every 3-4 months to maintain an instrument accuracy within specifications. Some regulatory requirements specify that a span calibration be carried out before each measurement. In that case you may find the EES portable calibration kit very useful.

A. THE ENERAC CALIBRATION PROTOCOL

To maintain the integrity and accuracy demanded of a regulatory compliance apparatus, the ENERAC 3000 has been given an extensive and comprehensive "calibration protocol", that will appear on its printer every time a calibration is carried out.

The protocol checks both instrument zero and span performance and serves to instill to the operator confidence on the integrity of his data.

1. The autozero protocol.

Every time the ENERAC is autozeroed, the performance of the sensors is checked to make sure that sensor zero baselines are within the prescribed limits.

If one or more of the sensors are outside the specified limits a message will appear on the display and printed simultaneously on the ENERAC's printer for documentation.

2. The span calibration protocol.

Since the calibration protocol checks the sensor's selectivity against interfering gases, you must always use SINGLE TOXIC GAS MIXTURES (i.e. do not use mixtures containing two of the following gases in one cylinder: carbon monoxide, nitric oxide, nitrogen dioxide and sulfur dioxide).

(The only exception to the SINGLE TOXIC GAS rule is to use a blend of NO and SO₂ gas bal. Nitrogen, in order to determine the performance of the NO sensor filter media. Cross interference of the NO sensor to SO₂ gas is detected only, if NO gas is present! Do not use, however, this blend to carry out any calibrations. Use it just to check sensor response.)

Every time the ENERAC is calibrated using span gas, a number of different parameters are checked for satisfactory performance.

The following messages appear always on the ENERAC printer:

"ENERAC CALIBRATION PROTOCOL"
" TIME: XX:XX:XX DATE: XX/XX/XX"

followed by a series of messages.

a. Air leak check.

The instrument is checked for air leaks during span calibration.

The air leak check is carried out only when calibrating the NO sensor, since NO span gas must always have zero oxygen.

If a leak is detected the following messages appear on the printer:

"SENSOR CALIBRATION FAILED"
"DETECTED SYSTEM AIR LEAK"

If an air leak is discovered, first check the gas connection to the tip of the probe to make sure that it is air tight. Following this, determine if the leak is in the probe or in the instrument. You can do this by passing the probe and feeding the gas to the instrument directly. Contact EES for further assistance.

b. Sensor sensitivity check.

The output of the sensor undergoing calibration is checked against its original sensitivity that has been stored in its memory. If the sensor's sensitivity is within the acceptable limits, the following message appears on the printer:

"SENSOR CALIBRATION SUCCESSFUL"
"XX SENSOR OK"

where XX refers to the sensor being calibrated.

If the sensor's sensitivity is slightly outside acceptable limits, but the sensor is still functioning properly, the following messages appear on the printer:

"SENSOR CALIBRATION SUCCESSFUL"
"REPLACE XX SENSOR SOON OR CHECK GAS"

The purpose of the last message is to warn the operator that the sensor might soon need replacement, or that the wrong span gas value has been entered accidentally.

Be careful when calibrating the NO₂ sensor with span gas. NO₂ span gas concentration deteriorates with time. Don't use any cylinders that are more than 6 months old. Buy from a reputable supplier. Don't use any external desiccants or water traps.

If the sensor's sensitivity is considerably outside acceptable limits, the sensor is considered as not functioning properly and should be replaced. The following messages appear on the printer:

"SENSOR CALIBRATION FAILED"
"REPLACE XX SENSOR OR CHECK SPAN GAS"

c. Sensor selectivity check.

The Precision Control Modules of the CO, NO and SO₂ sensors have long life inboard filters to remove any interfering gases that may be present in the

sample.

Filter life depends on the sensor, the concentration of the gas and exposure time of the interfering gas. Typically, for the ENERAC's SEM sensors it is 200,000 PPM-hours for the CO sensor and 20,000 PPM-hours for the NO sensor to NO₂ gas and 70000 PPM-hours to SO₂ gas.

If the cross sensitivity of the interfering gas rises to 2% for CO or 6% for NO the following warning message will appear on the printer:

"REPLACE XX SENSOR FILTER SOON"

If the cross sensitivity of the interfering gas rises further (i.e. 5% for the CO sensor) the following message will appear on the printer:

"REPLACE XX SENSOR FILTER "

Please keep in mind that irrespective of the inboard filter performance, the ENERAC mathematically compensates for any residual cross sensitivity, so that measurements can be taken with reasonable accuracy (but not compliance level accuracy), even if the filters need replacement.

B. AUTO ZEROING THE INSTRUMENT.

Every time you turn the instrument on, you should wait for 2 minutes for the ENERAC to warm up(OR UNTIL THE GREEN "PROBE OK LED TURNS ON). At the end of the warmup period the ENERAC reads the output of all sensors and sets them all to zero with the exception of the oxygen that it sets to 20.9%. (The ambient temperature is read directly). Consequently, it is very important that at the moment of "zeroing" the probe tip is at room temperature and the environment is clean from traces of carbon monoxide or other gases.

NOTE: In practice AUTOZEROING is only needed once at the beginning of a day of measurements. The ENERAC will not have sufficient zero drift during the next 24 hours to require additional autozeroing procedures.

You can bypass the AUTOZERO procedure by pressing any key other than the "ENTER" key, when prompted to do so by the display.

If the instrument has not been used for quite some time, it is a good idea to give it a longer warmup period. To do this turn the unit off at the end of its initial warmup and then turn it immediately back on.

If you accidentally shut off the unit, while the probe is still in the stack, turn the unit back on and bypass the Autozeroing procedure by pressing any key other than the

"Enter" key when the message "press enter to autozero" appears.

C. INSTRUMENT SPAN CALIBRATION.

Ideally, you should span calibrate the instrument every time you replace a Precision Control Module. At a minimum, once every 3-4 months you should perform a span calibration of the instrument. The parameters that require a span calibration are: carbon monoxide, combustibles, nitric oxide, nitrogen dioxide and sulfur dioxide.

There is, also, a span calibration for the ambient temperature sensor.

For instruments that have the stack-velocity (S-V) option, there is an additional calibration of the very low pressure sensor and a command to adjust the Pitot tube factor.

You can carry out all span calibrations in sequence or just one only, if you wish.

You can use your own span gas, or if you need to calibrate the ENERAC in the field, you can use the convenient gas calibration kit supplied by Energy Efficiency Systems.

1. Span calibration using the EES kit.

The gas calibration system supplied by EES is shown in Fig. 9. The kit comes with a gas cylinder containing a mixture of 200 PPM carbon monoxide (typically), 1.0% methane and balance nitrogen. For NO, NO₂ and SO₂ calibrations you must order extra gas cylinders containing the desired type of span gas. All four gas cylinders and apparatus fit inside a

carrying case for easy transportation to the field.




FIGURE 9

Follow the instructions supplied with the calibration kit for proper span calibration.

For the span calibration of the AMBIENT TEMPERATURE follow the directions in section 2 below.


2. Span calibration using your own gas.

If you wish to use your own gas to perform span calibrations you must take

certain precautions, in order to calibrate the sensors properly.

Preferably, for greatest accuracy it is recommended that you use a span gas value close to the emission concentration you expect to measure.

To carry out a span calibration USING YOUR OWN GAS APPARATUS



(Use single toxic gas mixture!)

FIGURE 10

follow the steps below:

1. Set up your calibration apparatus as shown in fig. 10.

Notice that you need a number of certified gas cylinders. Make sure you use the calibration accessory supplied with your instrument. The accessory ensures proper gas flow to the ENERAC.

You must not feed gas to the ENERAC under pressure and you must not starve the ENERAC's pump for gas. When feeding the gas to the ENERAC you must maintain the pressure reasonably constant. This is a requirement of all diffusion type sensors.

Connect the calibration accessory to the ENERAC probe. Make sure the rubber bulb is inserted past the square grooves located at the probe tip.

Connect the other end of the calibration accessory to the gas cylinder.

Make sure the concentration of the calibration gas is within the range of the Precision Control Module selected for each sensor. Do not under any circumstances, use gas that will over range the PCM. Preferably, do not calibrate with gas whose concentration is lower the PCM's range's lower boundary.

The Carbon Monoxide gas can be in the range 30-20000 PPM 2% accuracy with the balance nitrogen, preferably.

The Combustible gas can be in the range 0.07%-3.0% methane, 2% accuracy with the balance nitrogen or air.

The NO span gas can be in the range 10-3500 PPM, 2% accuracy with balance nitrogen.

The NO₂ span gas should be in the range 50-500 PPM, 2% accuracy balance air, preferably.

The sulfur dioxide span gas can be in the range of 30-7000 PPM, 2% accuracy, balance nitrogen, preferably.

If you plan to calibrate all sensors, follow the order of their appearance on the display. This is desirable in order to set the compensating matrix for cross sensitivities, properly.

2. Turn the instrument on, press ENTER to autozero and wait until the following message appears on the display:

"INSERT PROBE"

3. Push the "SET" button and observe "SET" LED turn on.
4. Push the "NO/NO2" button. The following message will appear:

"CMB SPAN GAS: 0.11%"

Step #5 below demonstrates how to bypass an unwanted span calibration and proceed to the next one.

5. (If you wish to skip the Combustibles calibration push the "ENTER" button. The display will read :

"PUSH ENTER KEY!!".

Press any button, except the "ENTER" button and the unit will skip the combustibles calibration and proceed to the next one.)

6. To carry out the combustibles span calibration, use the "UP" or "DOWN" buttons until the display reads the same combustibles value as that printed on the combustibles (methane) gas cylinder label. Then press the "ENTER" button. The following message will appear on the display:

"PRESS ENTER KEY!!"

7. Open the span gas valve and set your gas bypass flow (as indicated by the small flow meter of the calibration accessory) to 200-400 cc/min Make sure the flow rate indicated is reasonably constant. Press the "ENTER" key. The following message will appear on the display:

"FEED GAS NOW and WAIT"

8. Make sure you keep the gas flow reasonably constant by monitoring the flow meter. At the end of approximately three minutes the ENERAC will record and store the combustibles sensor response and define it as the value that you set earlier on the display.

When the following message appears on the display:

"CO SPAN GAS: 200 PPM"

it means that you are finished with the combustibles span calibration and the instrument is prompting you to perform the CO calibration next. Shut off the gas!

9. To carry out the CO (carbon monoxide) span calibration follow the procedure outlined above for the combustibles calibration.

A number of important messages, that are part of the "ENERAC CALIBRATION PROTOCOL", will appear on the printer at the end of the CO calibration.

If you wish to skip the CO sensor calibration proceed as in step 5. The following message will appear on the display:

"NO SPAN GAS: 200 PPM"

prompting you to carry out this calibration.

Please note that according to "ENERAC Calibration Protocol" this calibration also checks the performance of the CO sensor filter.

You may carry out or by pass this calibration, as you wish.

10. The next sensor calibration in line is sulfur dioxide and the following message will appear on the display;

"SO2 SPAN GAS: 200 PPM"

If you wish to carry out any of these calibrations, proceed as outlined in steps 6, 7 and 8.

IMPORTANT NOTE: SO2 AND NO2 gases are "sticky" gases. That means

that they tend to adsorb partially to the surface of materials causing a slow down of the response time of the instrument. For this reason, it is a good practice when calibrating with SO₂ or NO₂ span gases, to begin feeding the gas at least four minutes before executing the span calibration!

11. The last sensor calibration to be carried out is nitrogen dioxide and the following message will appear on the display:

"NO₂ SPAN GAS: 100 PPM"

prompting you to carry out this calibration in turn.

Please note that this span calibration also checks the performance of the NO sensor inboard filter and in addition, the performance of the SO₂ sensor according to the "ENERAC Calibration Protocol".

At the end of all span gas calibrations the following message will appear on the display:

"ATEMP OFFSET +0 C"

12. The final span calibration corrects for any inaccuracy in the ambient temperature reading. This calibration allows you to make minor corrections so that the ENERAC will read the exact ambient temperature.

You can only enter the correction in degrees Celsius. Use a good thermometer to compare with the ENERAC's ambient temperature reading and correct accordingly.

At the end of the span calibration procedure the following message will appear on the display:

"WAIT TWO MINUTES!!"

The instrument is now purging any traces of remaining gas.

At the end of the two minute period it will perform an "auto zero" and it will

be ready for measurements by displaying any two stack parameters.

NOTE: IF you wish to exit the span calibration procedure at any time, other than when the message "FEED GAS AND WAIT" is displayed simply press the "SET" key and observe the "SET LED" turn off.

Whenever the message "FEED GAS NOW AND WAIT" appears, the ENERAC is inside a software loop and will not respond to any keys or communicate with external computers. SHUT THE INSTRUMENT OFF, IF YOU HAVE TO ABORT A SPAN CALIBRATION.

INCREASED ACCURACY REQUIREMENTS

1. ALLOW THE INSTRUMENT TO REACH AMBIENT TEMPERATURE BEFORE CARRYING OUT A SPAN CALIBRATION OR MEASUREMENT.
2. FOR NO, NO₂ AND SO₂ CALIBRATIONS, FEED THE SPAN GAS FOR A MINIMUM OF 10 MINUTES BEFORE EXECUTING THE SPAN CALIBRATION PROCEDURE.
3. DURING A MEASUREMENT MAINTAIN THE SAME FLOW RATE INTO THE INSTRUMENT (+/- 10%) AS DURING SPAN CALIBRATION BY ADJUSTING THE SAMPLE PUMP VOLTAGE, IF NECESSARY.
4. TO ACHIEVE THE BEST MATHEMATICAL COMPENSATION, USE NO₂ SPAN GAS TO CALIBRATE, WHOSE CONCENTRATION IS APPROXIMATELY THE AVERAGE CONCENTRATION OF YOUR EXPECTED EMISSION.
5. CHECK THE NO FILTER INTERFERENCE REJECTION OF SO₂ GAS BY FEEDING A BLEND OF KNOWN CONCENTRATIONS OF NO AND SO₂ GASES.

MEASURED PARAMETERS:

1. AMBIENT TEMPERATURE. IC sensor. Degrees F or C.
Range: 0-150 degrees F
Resolution: 1 degree F or C.
Accuracy: 3 degrees F
2. STACK TEMPERATURE. Type K thermocouple. Degrees F or C
Range: 0-2000 degrees F (1100 C).
Resolution: 1 degree F.(1 C.)
Accuracy: 5 degrees F.
3. OXYGEN. Electrochemical cell. Life 2 years.
Range: 0-25%
Resolution: 0.1%
Accuracy: 0.2%
4. NITRIC OXIDE(NO). Electrochemical (SEM (TM)) cell. Life 2 years.
PCM Ranges: 0-300 PPM.
0-1000 PPM (300-1000)
0-3500 PPM (1000-3500)
Resolution: 1 PPM
Accuracy: 2% of reading (*)
5. NITROGEN DIOXIDE(NO₂). Electrochemical (SEM (TM)) cell. Life 2 years.
Range: 0-500 PPM.
Resolution: 1 PPM
Accuracy: 2% of reading (*)
6. CARBON MONOXIDE. Electrochemical (SEM (TM)) cell. Life 2 years.
PCM Ranges: 0-500 PPM.
0-2000 PPM (500-2000)
0-20000 PPM (2000-20000)
Resolution: 1 PPM

Accuracy: 2% of reading (*)

7. SULFUR DIOXIDE. Electrochemical (SEM (TM)) cell. Life 2 years.
PCM Ranges: 0-500 PPM.
 0-2000 PPM (500-2000)
 0-7000 PPM (2000-7000)
Resolution: 1 PPM
Accuracy: 2% of reading (*)

8. COMBUSTIBLES(GASES). Catalytic sensor. Life indefinite.
Range: 0-6.00%
Resolution: 0.01%
Accuracy: 10% of reading in CH₄ gas

9. TIME/DATE. Time in hours, minutes, seconds. Date in month, day, year format.

(*) When tested according to 40CFR60, RAA test.

COMPUTED PARAMETERS:

1. COMBUSTION EFFICIENCY. Heat loss method. Unique four loss factors computation.
(dry gas, water vapor, gaseous combustibles, combustibles in ash)
Range: 0-100%
Resolution: 0.1%
Accuracy(4 loss): 1% (above H₂O condensation)
 2% (below H₂O condensation)

2. CARBON DIOXIDE. Range: 0-40%
Resolution: 0.1%
Accuracy: 5% of reading.

3. EXCESS AIR. Range: 0-1000%
Resolution: 1%
Accuracy: 10% of reading

4. OXIDES OF NITROGEN. PCM Ranges: 0-800 PPM.
0-1500 PPM (800-1500)
0-4300 PPM (1500-4300)
Resolution: 1 PPM
Accuracy: 2% of reading (*)

5. EMISSIONS 1. Range: 0-2500 milligrams/cubic meter
(CO, NO, NO₂, NO_X, SO₂) Resolution: 2 mg/m³
Accuracy: 5% of reading

6. EMISSIONS 2. Range: 0.000-99.99 lbs./million BTU
(CO, NO, NO₂, NO_X, SO₂) Resolution: 0.01 lbs./MMBTU
Accuracy: 5% of reading
(Oxygen correction factor for emissions adjustable 0-20% in 1% steps plus TRUE).

7. EMISSIONS 3. Range: 0-99.99 grams/brake hp-hr
Resolution: 0.01 grms/bhp-hr
Accuracy: 10% of reading

PRINTER:

SEIKO 4", 40 char. per line thermal printer with form feed and line feed buttons and with end of paper override.

Operates in any of four print modes:

1. TEXT MODE. 25 line printout of instant. values of all measured parameters. (time req. 20 sec.)
2. PLOT MODE. Any one parameter vs. time plotted.
3 ordinate scales: full, half, quarter.
Time scale: Selectable, 1 sec/dot-1 min/dot in 1 sec/dot intervals.

APPENDIX I
Example Calculations

Example Calculations

1. Determine the mass emission flow rate (lbs/hr) of carbon monoxide from the SUE Incinerator during exhaust Sampling Run # 2.

$$E = (C) \times (MW) \times (FR) \times (1.55 \times 10^{-7})$$

Where,

E = The pollutant emission rate in pounds per hour (lb/hr)

C = The measured pollutant concentration in parts per million by volume (ppmv). For Run # 2, the average CO concentration was 108 ppmv.

MW = The molecular weight of the pollutant. For CO, MW = 28

FR = The flow rate of the stack gas in dry standard cubic feet per minute (DSCFM). The flow rate for Run # 2 (as calculated by EPA's HP 41 "Meth 2" Calculator Program) was 9,097 DSCFM.

1.55×10^{-7} = Conversion Factor $[(\text{min} \cdot \text{g-mole} \cdot \text{lb}) / (\text{hr} \cdot \text{g} \cdot \text{ft}^3)]$

$$E = (108) (28 \text{ g/g-mole}) (9,097 \text{ ft}^3/\text{min}) (1.55 \times 10^{-7} \text{ min} \cdot \text{g-mole} \cdot \text{lb}/\text{hr} \cdot \text{g} \cdot \text{ft}^3)$$

$$\mathbf{E = 4.3 \text{ lbs/hr}}$$

2. Determine the VOC destruction efficiency of the SUE Incinerator during exhaust Sampling Run #1.

$$DE = [(CF - E_{ex}) / CF] \times 100$$

Where,

DE = Destruction Efficiency (%)

CF = Calibration fluid combusted by the SUE Incinerator (lb/hr as Stoddard solvent). This includes both the VOC vapors in the inlet gas stream and the liquid waste calibration fluid burned as supplemental fuel.

E_{ex} = VOC emission rate in exhaust stack (lb/hr as Stoddard solvent).

Since the SUE Incinerator burned liquid waste calibration fluid, it is necessary to determine both the inlet and exhaust VOC mass flow rates in units of "lbs/hr as Stoddard solvent" instead of "lbs/hr as propane." This is done by converting the measured concentrations from "ppmv as propane" to "ppmv as Stoddard solvent" using the following equation:

$$\text{ppmv as Stoddard solvent} = [(\text{ppmv as propane}) \times (3)] / 7.05$$

Where,

3 = the carbon equivalent correction factor (listed in EPA Method 25A) which converts "ppmv as propane" to "ppmv as carbon"
 7.05 = response factor (determined by a contractor during previous VOC emissions testing at Kelly AFB) for converting "ppmv as carbon" to "ppmv as Stoddard solvent)

$$\text{Average inlet VOC concentration} = (149 \text{ ppmv as propane}) (3) (1/7.05) \\ = 63.4 \text{ ppmv as Stoddard solvent}$$

$$\text{Run 1 exhaust VOC concentration} = (14.7 \text{ ppmv as propane}) (3) (1/7.05) \\ = 6.3 \text{ ppmv as Stoddard solvent}$$

The inlet and exhaust VOC mass emission rates (in lbs/hr as Stoddard solvent) are then calculated as follows:

$$E = (C) \times (MW) \times (FR) \times (1.55 \times 10^{-7})$$

Where,

E = The pollutant emission rate (lbs/hr as Stoddard solvent)
 C = The pollutant concentration (ppmv as Stoddard solvent)
 MW = The molecular weight of the pollutant. For Stoddard solvent, MW = 140
 FR = The flow rate of the gas stream (DSCFM). The average inlet flow rate (as calculated by EPA's HP 41 "Meth 2" Calculator Program) was 10,085 DSCFM. The Run 1 exhaust flow rate (as calculated by EPA's HP 41 "Meth 2" Calculator Program) was 9,155 DSCFM.
 1.55×10^{-7} = Conversion Factor $[(\text{min} \cdot \text{g-mole} \cdot \text{lb}) / (\text{hr} \cdot \text{g} \cdot \text{ft}^3)]$

$$E \text{ (in)} = (63.4) (140 \text{ g/g-mole}) (10,085 \text{ ft}^3/\text{min}) (1.55 \times 10^{-7} \text{ min} \cdot \text{g-mole} \cdot \text{lb}/\text{hr} \cdot \text{g} \cdot \text{ft}^3) \\ = 13.9 \text{ lbs/hr as Stoddard solvent}$$

$$E \text{ (ex)} = (6.3) (140 \text{ g/g-mole}) (9,155 \text{ ft}^3/\text{min}) (1.55 \times 10^{-7} \text{ min} \cdot \text{g-mole} \cdot \text{lb}/\text{hr} \cdot \text{g} \cdot \text{ft}^3) \\ = 1.25 \text{ lbs/hr as Stoddard solvent}$$

The average inlet VOC mass flow rate (13.9 lbs/hr as Stoddard solvent) is then added to the liquid waste Stoddard solvent combusted during exhaust Sampling Run # 1 (108 lbs/hr) to obtain the approximate amount of total calibration fluid (121.9 lbs/hr) combusted during Run # 1. The destruction efficiency can now be calculated as follows:

$$DE = [(121.9 \text{ lb/hr} - 1.25 \text{ lbs/hr}) / 121.9 \text{ lbs/hr}] \times 100$$

$$DE = 99.0\%$$